

United States Environmental Protection Agency
Washington, DC 20460

Completion Form For Injection Wells

Administrative Information

1. Permittee Florence Copper Inc.

Address (Permanent Mailing Address) (Street, City, and ZIP Code)

1575 W Hunt Hwy, Florence, AZ 85132

2. Operator Florence Copper Inc.

Address (Street, City, State and ZIP Code)

1575 W Hunt Hwy, Florence, AZ 85132

3. Facility Name Florence Copper Inc. Telephone Number (520) 374-3984

Address (Street, City, State and ZIP Code)

1575 W Hunt Hwy, Florence, AZ 85132

4. Surface Location Description of Injection Well(s)

State Arizona County Pinal

Surface Location Description

Nw 1/4 of SW 1/4 of NE 1/4 of SW 1/4 of Section 28 Township 4S Range 9E

Locate well in two directions from nearest lines of quarter section and drilling unit

Surface

Location 955 ft. frm (N/S) N Line of quarter section
and 1175 ft. from (E/W) E Line of quarter section.

Well Activity

- ☐ Class I
☐ Class II
☐ Brine Disposal
☐ Enhanced Recovery
☐ Hydrocarbon Storage
☒ Class III
☐ Other

Well Status

- ☒ Operating
☐ Modification/Conversion
☐ Proposed

Type of Permit

- ☐ Individual
☒ Area : Number of Wells 33

Lease Number NA

Well Number M55-UBF

Submit with this Completion Form the attachments listed in Attachments for Completion Form.

Certification

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment (Ref. 40 CFR 144.32)

Name and Official Title (Please type or print)

Ian Ream, Senior Hydrogeologist

Signature

Date Signed

9-12-2018

PAPERWORK REDUCTION ACT

The public reporting and record keeping burden for this collection of information is estimated to average 49 hours per response for a Class I hazardous facility, and 47 hours per response for a Class I non-hazardous facility. Burden means the total time, effort, or financial resource expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal Agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to the collection of information; search data sources; complete and review the collection of information; and, transmit or otherwise disclose the information. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques to Director, Collection Strategies Division, U.S. Environmental Protection Agency (2822), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed forms to this address.

Attachments to be submitted with the Completion report:

I. Geologic Information

1. Lithology and Stratigraphy

A. Provide a geologic description of the rock units penetrated by name, age, depth, thickness, and lithology of each rock unit penetrated.

B. Provide a description of the injection unit.

- (1) Name
- (2) Depth (drilled)
- (3) Thickness
- (4) Formation fluid pressure
- (5) Age of unit
- (6) Porosity (avg.)
- (7) Permeability
- (8) Bottom hole temperature
- (9) Lithology
- (10) Bottom hole pressure
- (11) Fracture pressure

C. Provide chemical characteristics of formation fluid (attach chemical analysis).

D. Provide a description of freshwater aquifers.

- (1) Depth to base of fresh water (less than 10,000 mg/l TDS).
- (2) Provide a geologic description of aquifer units with name, age, depth, thickness, lithology, and average total dissolved solids.

II. Well Design and Construction

1. Provide data on surface, intermediate, and long string casing and tubing. Data must include material, size, weight, grade, and depth set.
2. Provide data on the well cement, such as type/class, additives, amount, and method of emplacement.
3. Provide packer data on the packer (if used) such as type, name and model, setting depth, and type of annular fluid used.

4. Provide data on centralizers to include number, type and depth.

5. Provide data on bottom hole completions.

6. Provide data on well stimulation used.

III. Description of Surface Equipment

1. Provide data and a sketch of holding tanks, flow lines, filters, and injection pump.

IV. Monitoring Systems

1. Provide data on recording and nonrecording injection pressure gauges, casing-tubing annulus pressure gauges, injection rate meters, temperature meters, and other meters or gauges.

2. Provide data on constructed monitor wells such as location, depth, casing diameter, method of cementing, etc.

V. Logging and Testing Results

Provide a descriptive report interpreting the results of geophysical logs and other tests. Include a description and data on deviation checks run during drilling.

VI. Provide an as-built diagrammatic sketch of the injection well(s) showing casing, cement, tubing, packer, etc., with proper setting depths. The sketch should include well head and gauges.

VII. Provide data demonstrating mechanical integrity pursuant to 40 CFR 146.08.

VIII. Report on the compatibility of injected wastes with fluids and minerals in both the injection zone and the confining zone.

IX. Report the status of corrective action on defective wells in the area of review.

X. Include the anticipated maximum pressure and flow rate at which injection will operate.

TECHNICAL MEMORANDUM

17 September 2018
File No. 129687-010

TO: Florence Copper Inc.
Ian Ream, Senior Hydrogeologist

FROM: Haley & Aldrich, Inc.
Lauren Candreva, R.G.

Subject: Drilling, Installation, and Integrity Testing Summary
PTF Supplemental Monitoring Well M55-UBF
Florence Copper Inc., Florence, Arizona



This document summarizes the drilling, installation, and testing of Production Test Facility (PTF) supplemental monitoring well M55-UBF for Florence Copper Inc. (Florence Copper) in Florence, Arizona, including the equipment used to perform the work, completion, and the results of well testing activities. Separate well completion reports have been created for each PTF well.

The Arizona Department of Water Resources Registry ID for well M55-UBF is 55-226797; the Well Registry Report is included in Appendix A. The well is located in the southeast quarter of the northwest quarter of the southwest quarter of Section 28 of Township 4 north, Range 9 East of the Gila and Salt River Baseline and Meridian (D(4-9)28CBD). The well is located within the Underground Injection Control (UIC) Permitted Area of Review (AOR) for UIC Permit R9UIC-AZ3-FY11-1 and was completed as a Class III supplemental monitoring well for the PTF (Figure 1).

Florence Copper contracted National Exploration, Wells, and Pumps (National) to drill, install, and test well M55-UBF in accordance with *Bid Specification: Installation, of Class III Monitoring Wells, Production Test Facility, Florence, Arizona* (Haley & Aldrich, Inc. [Haley & Aldrich], 2015). A Schramm T685WS drilling rig was used for all drilling and construction activities. Haley & Aldrich provided intermittent oversight of drilling activities and provided complete oversight during key activities such as geophysical logging, well installation, and testing. All reported depths are in feet below ground surface unless otherwise noted.

I. Geologic Information

1. Lithology and Stratigraphy

A. Geology of Penetrated Units

The geology penetrated during the drilling of the Class III well M55-UBF is summarized below, and a lithologic log is included in Appendix B.

Lithologic Unit Name	Depth to Bottom of Unit (feet)	Thickness of Unit (feet)	Lithology and Age of Unit
Upper Basin Fill Unit (UBFU)	Not encountered	>272	Alluvium; Quaternary to Tertiary

B. Description of Injection Unit

Well M55-UBF is a supplemental monitoring well completed in the UBFU. The bottom of the well is approximately 150 feet above the top of the permitted injection zone.

C. Chemical Characteristics of Formation Fluid

The chemical characteristics of the formation fluid in the injection zone are summarized below and are the sampling results from the center PTF wellfield well, R-09. The table below summarizes the primary chemical characteristics detected in a formation fluid sample collected on 23 April 2018; the complete analytical report is included in Appendix C.

Analyte	Result (mg/L)
Metals	
Aluminum	<0.08
Antimony	<0.005
Arsenic	0.0016
Barium	0.071
Beryllium	<0.0005
Cadmium	<0.00025
Calcium	140
Chromium	0.0051
Cobalt	<0.00025
Copper	0.011
Iron	<0.30
Lead	<0.0005
Magnesium	27
Manganese	0.002
Mercury	<0.001
Nickel	0.0033
Potassium	6.8
Selenium	<0.0025
Sodium	170

Analyte	Result (mg/L)
Thallium	<0.0005
Zinc	<0.04
Anions	
Bicarbonate	150
Chloride	310
Fluoride	<0.5
Nitrate	8.8
Sulfate	190
Field Parameters	
Total Dissolved Solids	1,000
pH	7.8
Radiochemicals	
Uranium	0.016
Notes: mg/L = milligrams per liter	

The water quality of each PTF monitoring well, including well M55-UBF, is summarized in *Procedures for Determining Alert Levels and Aquifer Quality Limits for Groundwater Compliance Monitoring* (Brown and Caldwell, 2018).

D. Description of Freshwater Aquifers

- 1) The depth to the base of the freshwater aquifer is defined by the interface where deeper formation fluid exhibits a total dissolved solids (TDS) value of 10,000 milligrams per liter (mg/L). The depth of the 10,000 mg/L interface is deeper than all of the wells drilled at the site and consequently has not been defined.
- 2) A geologic description of the aquifer units encountered in M55-UBF is included below:

Aquifer Unit Name	Age	Depth (feet)	Thickness (feet)	Lithology	Average Total Dissolved Solids ¹ (mg/L)
UBFU	Quaternary/Tertiary	0 to 272	>272	Alluvium	914

¹ Average TDS values calculated from UBFU and LBFU monitoring well ambient monitoring results near the PTF.

II. Well Design and Construction

1. Well M55-UBF Casing Installed

Casing	Material	Diameter (inches)	Weight (pounds per foot)	Depths (feet)	Borehole Diameter (inches)	Drilling Method
Surface	Mild steel	14 O.D. 13 $\frac{3}{8}$ I.D.	47.36	0 to 40	17 $\frac{1}{2}$	Conventional mud rotary
Well casing	Mild steel	5.66 O.D. 5.14 I.D.	5.40	-1.3 to 240	10 $\frac{5}{8}$	Conventional mud rotary
Screen	PVC Sch. 80 with 0.020-inch wide slots	5.56 O.D. 4.81 I.D.	4.08	240 to 260	10 $\frac{5}{8}$	Conventional mud rotary
Notes: <i>I.D. = inside diameter</i> <i>O.D. = outside diameter</i> <i>PVC = polyvinyl chloride</i> <i>Sch. = Schedule</i>						

2. Well Cement

Cement Interval	Cement Type	Additives	Amount Installed (cubic yards)	Method of Emplacement
Surface casing	Type V Neat 21 sack slurry	None	1.5 ¹	Submerged tremie
Well casing	Type V Neat 21 sack slurry	None	5.1	Submerged tremie
¹ Cement was mixed on-site and installed by drilling contractor, volume estimated.				

Field forms documenting pipe tallies, annular materials, and cement tickets are included in Appendix D.

3. Annular Packers

No annular packers were used during construction of well M55-UBF.

4. Centralizers

Casing	Centralizer Type	Number and Spacing
Well – Mild Steel and PVC	Stainless steel – heavy duty	6 installed – every 40 feet
Notes: <i>PVC = polyvinyl chloride</i>		

5. Bottom Hole Completion

There is no bottom hole completion, as this is not an oil/gas well. The well was completed at the bottom with a stainless-steel endcap of the same diameter as the well screen.

6. Well Stimulation

No well stimulation was used during the drilling and construction of well M55-UBF.

III. Description of Surface Equipment

1. Surface Equipment

Well M55-UBF is a supplemental monitoring well and has been equipped with a pressure transducer for monitoring water levels and a low-flow pump for collecting water quality samples. There is no surface equipment beyond the well casing stick-up and locking well vault. An as-built diagram of the well is included as Figure 2.

IV. Monitoring Systems

1. Well Monitoring Equipment

Well M55-UBF is a monitoring well and does not have any monitoring systems for injection. A pressure transducer with a data logger is installed in the well to collect water levels for compliance reporting.

2. Monitoring Wells

A total of 16 monitoring wells (including well M55-UBF) are associated with the PTF: 7 point of compliance (POC) wells, 7 United States Environmental Protection Agency (USEPA) supplemental monitoring wells, and 2 operational monitoring wells. The POC wells are located outside the AOR and are not constructed as Class III wells. The supplemental monitoring and operational monitoring wells are located within the AOR and are constructed as Class III wells as required by the UIC Permit. The wells are summarized in the tables below by type.

POC Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval (feet)	Screened Lithologic Unit
M14-GL	846750.23 746461.52	859	5 9/16 OD	Submerged tremie	778 to 838	LBFU
M15-GU	846697.17 746464.82	615	5 9/16 OD	Submerged tremie	554 to 594	LBFU

POC Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval (feet)	Screened Lithologic Unit
M22-O	846751.26 746514.47	1,140	5 9/16 OD to 528 feet; 4½ OD to 1,140 feet	Submerged tremie	932 to 1,130	Oxide
M23-UBF	846688.13 746512.48	250	6¾ OD	Submerged tremie	210 to 250	UBFU
M52-UBF	851092.00 774178.00	274	5 9/16	Submerged tremie	198 to 273	UBFU
M54-LBF	847331.96 746682.61	630	5 9/16	Submerged tremie	310 to 629	LBFU
M54-O	847342.99 746702.36	1,199	5 9/16	Submerged tremie	668 to 1,198	Oxide
OD = outside diameter						

Supplemental Monitoring Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval (feet)	Screened Lithologic Unit
M55-UBF	847541.46 746280.63	261	5	Submerged tremie	240 to 260	UBFU
M56-LBF	847518.70 746303.41	340	5	Submerged tremie	320 to 340	LBFU
M57-O	847378.37 746248.93	1,200	5	Submerged tremie	523 to 1,199	Oxide
M58-O	847672.23 746595.97	1,200	5	Submerged tremie	594 to 1,199	Oxide
M59-O	847934.95 746218.89	1,201	5	Submerged tremie	534 to 1,199	Oxide
M60-O	847599.37 745903.70	1,201	5	Submerged tremie	444 to 1,200	Oxide
M61-LBF	848184.46 746148.88	629	5	Submerged tremie	429 to 629	LBFU

Operational Monitoring Wells						
Well ID	Location X/Y (State Plane NAD 83)	Depth (feet)	Well Nom. Diameter (inches)	Cementing Method	Screened Interval	Screened Lithologic Unit
MW-01-LBF	847487.97 746360.54	444	5	Submerged tremie	330 to 440	LBFU
MW-01-O	847499.04 746369.31	1,200	5	Submerged tremie	500 to 1,200	Oxide

V. Logging and Testing Results

Borehole geophysical logging was conducted on well M55-UBF in two phases: 1) open-hole surveys in the 12.25-inch borehole prior to installation of the well casing and screen, and 2) cased-hole surveys in the completed well.

The open-hole geophysical surveys completed at M55-UBF included:

- Spontaneous potential;
- Natural gamma;
- Electrical resistivity (short and long normal);
- Caliper with calculated volume;
- Temperature;
- Sonic; and
- Deviation.

The cased-hole geophysical surveys completed included:

- Sonic (for cement bond with fiberglass reinforced plastic [FRP]);
- 4 pi density (for cement bond with FRP); and
- Dual density (for cement bond with FRP).

Open-hole geophysical surveys were used to support identification of the lithologic contacts, to evaluate the condition of the borehole, and to evaluate the deviation of the borehole.

The primary logs used to evaluate lithologic contacts were natural gamma ray, short (16-inch) and long (64-inch) normal electrical resistance, and single-point resistance.

No contacts were identified with the logging conducted at M55-UBF. The well was completed within the shallowest unit at the site, the Upper Basin Fill Unit (UBFU).

Cased-hole geophysical surveys were conducted to evaluate the cement seal and the casing-cement bond, to document baseline fluid temperature and conductivity, and to evaluate the plumbness of the well. The cement bond is discussed in Section VII.

Copies of all the geophysical logs are included in Appendix E; a figure summarizing the open-hole logs used to evaluate the geology is included as Figure 3.

VI. Well As-Built Diagram

An as-built diagram for well M55-UBF is included as Figure 2.

VII. Demonstration of Mechanical Integrity

A demonstration of Part I mechanical integrity of the well was completed using a standard annular pressure test (SAPT) in accordance with Part II.E.3.a.i.A of the UIC Permit. Mechanical integrity will be demonstrated every 2 years during operations. The SAPT for well M55-UBF is summarized below.

The SAPT was conducted by installing an inflatable packer in the well secured with a threaded well seal at the surface. The packer was installed near the bottom of the FRP-cased portion of the well and the wellhead was equipped with a water-tight threaded wellhead; the packer was inflated to form a seal against the casing. The bottom 5 feet of the packer drop pipe was perforated to allow for communication between the tubing and the annulus of the packer assembly. The drop pipe extended through the wellhead and a high pressure/low volume pump was attached to the drop pipe to pressurize the test interval. A valve on the drop pipe at the surface was used to isolate the test interval once the planned test pressure was achieved.

An In-Situ LevelTROLL® pressure transducer with a data logger was installed at the well head and connected to the packer assembly annulus interval via a National Pipe Thread adapter. The LevelTROLL was used to monitor and record pressure inside the well during the SAPT. To conduct the SAPT, water was pumped from a nearby well immediately prior to testing. Before the water was pumped into the test well, the water temperature was measured to ensure that it was similar to the ambient groundwater temperature of the test well to reduce the potential for differential temperature effects on the well casing. The SAPT for the Class III well was conducted by applying hydraulic pressure to the well casing and shutting in pressure between the packer and wellhead assembly, monitoring the shut-in pressure for a 30-minute period, then measuring the volume of water returned from the well casing after the pressure was released.

On 23 June 2017, the packer was installed to approximately 199 feet; the SAPT was unsuccessful. The USEPA SAPT form summarizing the results of the test is provided in Appendix F.

Part II mechanical integrity is demonstrated by the cementing records included in this report (in accordance with Part II.E.3.ii.C of the UIC Permit) and will be demonstrated during operations by annular conductivity monitoring on the observation and multi-level sampling wells (in accordance with Part II.E.3.a.ii.A of the UIC Permit).

Cemented Interval	Cement Type	Calculated Grout Volume (cubic yards)	Installed Grout Volume (cubic yards)
Surface casing	Type V 21 sack neat cement slurry	0.9	1.5 ¹
Well casing	Type V 21 sack neat cement slurry	3.9	5.1

¹ Cement was mixed on-site and installed by drilling contractor, volume estimated.

On 12 May 2017, a cement bond log, density, and gamma logs were run over the entire length of the completed well to verify the grout seal. A summary of the logs completed to demonstrate cement bond are included in Appendix G.

For well M55-UBF, a cement bond survey was completed but due to the limited saturated interval of the well, the data were not useful in evaluating the cement seal. In addition to the cement bond log, density surveys were completed including focused density, sonic, and 4pi density. The measured density of the cased interval at well M55-UBF are consistent and indicate there are no significant cement deficiencies at well M55-UBF. A summary of the cased hole geophysical data is included in the well completion summary for well M55-UBF in Appendix G.

VIII. Compatibility of Injected Waste

The Florence Copper Project is a Class III mineral extraction project and does not include the injection of any waste products of any kind. The injected fluid (lixiviant) is a carefully constituted in-situ copper recovery solution that will be recovered and recycled following injection.

The compatibility of the lixiviant was evaluated as part of the geochemical modeling completed by Florence Copper and summarized in the *Geochemical Evaluation to Forecast Composition of Process Solutions for In-Situ Copper Recovery Pilot Test Facility at Florence Copper, Florence Arizona* (Daniel B. Stephens Inc., 2014) which was included in Attachment H of the UIC Permit Application.

IX. Status of Corrective Action on Defective Wells in the Area of Review

There are not currently any defective wells in the AOR.

X. Maximum Pressures and Flow Rates for M55-UBF

Maximum Operating Pressure	Maximum Flow
Atmospheric	Not applicable – monitoring well

This well is a monitoring well used to monitor water quality near the PTF. No fluids will be injected.

XI. Well Development

Well M55-UBF was initially developed by the airlift method followed by pump development. Development activities were completed by National using a workover rig. On 24 April 2017, an airline was temporarily installed to 257 feet and airlift development of the well was conducted over a period of 2 days at approximately 2 gallons per minute (gpm) to purge drilling fluids and solids from the well. During airlift development, the airlift pump was turned on and off to surge the well. Near the end of airlift development on 25 April 2017, approximately 0.25 gallon of AquaClear PFD® polymer dispersant was swabbed into the screened interval of the well. Airlift development resumed on 1 May 2017 for approximately one hour. The discharge was turbid but sand-free at the end of the airlift development period.

To pump develop the well, on 1 May 2017 a submersible pump was temporarily installed to a depth of 255 feet. Prior to pumping, the static water level was approximately 235 feet. Pump development was conducted at approximately 10 to 20 gpm; the submersible pump was periodically turned off to surge the well during development. The discharge was sand-free and visually clear after approximately 45 minutes of pump development; however, development was conducted over a period of 2 days. The development was concluded on 2 May 2017, at which time the discharge was sand-free with turbidity values less than 5 Nephelometric Turbidity Units. Well development forms are included in Appendix H.

XII. Well Completion

The surveyed location for well M55-UBF is as follows:

Northing (feet)	Easting (feet)	Measuring Point Elevation (feet amsl)
746280.63	847541.46	1479.14
Notes: <i>Northing and easting locations provided in State Plane North American Datum 1983; vertical location provided in North American Vertical Datum 1988. amsl = above mean sea level</i>		

XIII. Downhole Equipment

Permanent equipment installed in well M55-UBF includes the following:

- QED® low-flow sampling pump hung on drop tubing (pump at 250 feet); and
- Pressure transducer.

The type and depth of equipment installed in each well is not constrained by the UIC Permit or the Aquifer Protection Permit (APP). This information is provided in accordance with Section 2.7.4.3 of the APP. Operational considerations may require that the type and depth of equipment be changed in response to conditions observed during operations.

XIV. References

Brown and Caldwell, Inc., 2018. *Procedures for Determining Alert Levels and Aquifer Quality Limits for Groundwater Compliance Monitoring, Florence Copper Project, Florence, Arizona*. June.

Daniel B. Stephens, Inc., 2014. *Geochemical Evaluation to Forecast Composition of Process Solutions for In-Situ Copper Recovery Pilot Test Facility at Florence Copper, Florence Arizona*. Prepared for Florence Copper. May.




Haley & Aldrich, Inc., 2017. *Bid Specification: Installation, of Class III Monitoring Wells, Production Test Facility, Florence, Arizona*. Revised September 2017.

Enclosures:

- Figure 1 – Well Locations
- Figure 2 – M55-UBF Supplemental Monitoring Well As-Built Diagram
- Figure 3 – Geophysical Data and Lithologic Log
- Appendix A – Arizona Department of Water Resources Well Registry Report
- Appendix B – Lithologic Log
- Appendix C – Chemical Characteristics of Formation Water
- Appendix D – Well Completion Documentation
- Appendix E – Geophysical Logs
- Appendix F – SAPT Documentation
- Appendix G – Cement Bond Log Summary
- Appendix H – Well Development Field Forms


FIGURES


GIS FILE PATH: G:\Projects\Florence Copper\129687 PTF Well Drilling\GIS\Maps\2018_07129687_010_A001_WELL_LOCATIONS.mxd — USER: dfm — LAST SAVED: 7/17/2018 10:24:09 AM



NOTES

- ALL LOCATIONS AND DIMENSIONS ARE APPROXIMATE.
- AERIAL IMAGERY SOURCE: ESRI





NOTES

1. WELL REGISTRATION NO.: 55-226797
2. CADASTRAL LOCATION: D (4-9) 28 CBD
3. TOP OF CASING ELEVATION: 1479.14' AMSL
4. CONCRETE PAD ELEVATION: 1478.00' AMSL
5. I.D. = INSIDE DIAMETER
6. O.D. = OUTSIDE DIAMETER
7. PVC = POLYVINYL CHLORIDE

**HALEY
ALDRICH**


PRODUCTION TEST FACILITY
FLORENCE COPPER, INC.
FLORENCE, ARIZONA

M55-UBF SUPPLEMENTAL MONITORING WELL AS-BUILT DIAGRAM

**FLORENCE
COPPER INC.**

SCALE: NOT TO SCALE
DECEMBER 2018

FIGURE 2



HALEY
ALDRICH

PRODUCTION TEST FACILITY
FLORENCE COPPER, INC.
FLORENCE, ARIZONA

M55-UBF SUPPLEMENTAL MONITORING
WELLGEOPHYSICAL DATA AND
LITHOLOGIC LOG

FLORENCE
COPPER

SCALE: AS SHOWN
SEPTEMBER 2018

FIGURE 3

APPENDIX A

Arizona Department of Water Resources Well Registry Report



Arizona Department of Water Resources
Information Management Unit
PO Box 36020 • Phoenix, Arizona 85067-6020
(602) 771-8527 • 602-771-8500

Well Driller Report and Well Log

9/20/17

THIS REPORT MUST BE FILED WITHIN 30 DAYS OF COMPLETING THE WELL.
PLEASE PRINT CLEARLY USING BLACK OR BLUE INK

FILE NUMBER
D(4-9) 28 CBD
WELL REGISTRATION NUMBER
55 - 226797
PERMIT NUMBER (IF ISSUED)

SECTION 1. DRILLING AUTHORIZATION

Drilling Firm

Mail To:

NAME
NATIONAL EWP, INC.

ADDRESS
1200 W. SAN PEDRO ST.

CITY / STATE / ZIP
GILBERT, AZ, 85233

DWR LICENSE NUMBER
823

TELEPHONE NUMBER
480-558-3500

FAX

RECEIVED

AUG 9 2017

ARIZONA DEPARTMENT
OF WATER RESOURCES

SECTION 1. REGISTRY INFORMATION

Well Owner

FULL NAME OF COMPANY, ORGANIZATION, OR INDIVIDUAL
FLORENCE COPPER, INC.

MAILING ADDRESS
1575 W. HUNT HWY

CITY / STATE / ZIP
FLORENCE, AZ, 85132

CONTACT PERSON NAME AND TITLE
Ian Ream, Senior Hydrogeologist

TELEPHONE NUMBER
520 374-3984

FAX

WELL NAME (e.g., MW-1, PZ-3, lot 25 Well, Smith Well, etc.)
M55-UBF

Location of Well

WELL LOCATION ADDRESS (IF ANY)
Same as well owner

TOWNSHIP (N/S) 4S RANGE (E/W) 9E SECTION 28 160 ACRE SW 1/4 40 ACRE NW 1/4 10 ACRE SE 1/4

LATITUDE 33 LONGITUDE 111 26 6

METHOD OF LATITUDE/LONGITUDE (CHECK ONE)
☒ *GPS: Hand-Held
☐ USGS Quad Map ☐ Conventional Survey ☐ *GPS: Survey-Grade

LAND SURFACE ELEVATION AT WELL
1477 Feet Above Sea Level

METHOD OF ELEVATION (CHECK ONE)
☒ *GPS: Hand-Held
☐ USGS Quad Map ☐ Conventional Survey ☐ *GPS: Survey-Grade

*IF GPS WAS USED, GEOGRAPHIC COORDINATE DATUM (CHECK ONE)

☒ NAD-83 ☐ Other (please specify)

COUNTY

Pinal

ASSESSOR'S PARCEL ID NUMBER (MOST RECENT)

BOOK 0 MAP 0 PARCEL 0

SECTION 3. WELL CONSTRUCTION DETAILS

Drilling Method

CHECK ONE
☐ Air Rotary
☐ Bored or Augered
☐ Cable Tool
☐ Dual Rotary
☒ Mud Rotary
☐ Reverse Circulation
☐ Driven
☐ Jetted
☐ Air Percussion / Odex Tubing
☐ Other (please specify)

Method of Well Development

CHECK ONE
☒ Airlift
☐ Bail
☐ Surge Block
☐ Surge Pump
☐ Other (please specify)

Condition of Well

CHECK ONE
☐ Capped
☒ Pump Installed

Method of Sealing at Reduction Points

CHECK ONE
☒ None
☐ Packed
☐ Swedged
☐ Welded
☐ Other (please specify)

Construction Dates

DATE WELL CONSTRUCTION STARTED
4.11.2017

DATE WELL CONSTRUCTION COMPLETED
4.11.2017

I state that this notice is filed in compliance with A.R.S. § 45-596 and is complete and correct to the best of my knowledge and belief.

SIGNATURE OF QUALIFYING PARTY

DATE

8-3-17

WELL REGISTRATION NUMBER
55 - 226797

Depth

DEPTH OF BORING	270	Feet Below Land Surface	DEPTH OF COMPLETED WELL	260	Feet Below Land Surface
-----------------	-----	-------------------------	-------------------------	-----	-------------------------

233	Feet Below Land Surface	5.02.2017	12:00	<input type="checkbox"/> Valve <input type="checkbox"/> Other:
-----	-------------------------	-----------	-------	--

[illegible]

ANNULAR MATERIAL TYPE (T)

[illegible]

Well Driller Report and Well Log

WELL REGISTRATION NUMBER
55 - 226797

SECTION 5. GEOLOGIC LOG OF WELL

[illegible]

Well Driller Report and Well Log

WELL REGISTRATION NUMBER
55 - 226797

SECTION 6. WELL SITE PLAN

NAME OF WELL OWNER

FLORENCE COPPER, INC.



COUNTY ASSESSOR'S PARCEL ID NUMBER (MOST RECENT)

BOOK

MAP

PARCEL

- ❖ Please draw the following: (1) the boundaries of property on which the well was located; (2) the well location; (3) the locations of all septic tank systems and sewer systems on the property or within 100 feet of the well location, even if on neighboring properties; and (4) any permanent structures on the property that may aid in locating the well.
- ❖ Please indicate the distance between the well location and any septic tank system or sewer system.

Run Date: 01/13/2017

AZ DEPARTMENT OF WATER RESOURCES
WELL REGISTRY REPORT - WELLS55

Location D 4.0 9.0 28 C B D	Well Reg.No 55 - 226797	AMA PINAL AMA
Registered Name FLORENCE COPPER, INC. 1575 W. HUNT HWY	File Type NEW WELLS (INTENTS OR APPLICATIONS)	Application/Issue Date 01/11/2017
FLORENCE	AZ 85132	
Owner OWNER	Well Type ENV - MONITOR	
Driller No. 823	SubBasin ELOY	
Driller Name NATIONAL EWP, INC.	Watershed UPPER GILA RIVER	
Driller Phone 480-558-3500	Registered Water Uses MONITORING	
County PINAL	Registered Well Uses MONITOR	
	Discharge Method NO DISCHARGE METHOD LISTED	
Intended Capacity GPM 0.00	Power NO POWER CODE LISTED	
Well Depth 0.00	Case Diam 0.00	Tested Cap 0.00
Pump Cap. 0.00	Case Depth 0.00	CRT
Draw Down 0.00	Water Level 0.00	Log
	Acres Irrig 0.00	Finish NO CASING CODE LISTED
Contamination Site: NO - NOT IN ANY REMEDIAL ACTION SITE		
Tribe: Not in a tribal zone		
Comments Well M55-UBF Landownership: AZ State Land Dept. (Mineral Lease #11-026500) TV		
Current Action		
1/13/2017	555	DRILLER & OWNER PACKETS MAILED
Action Comment: TNV		
Action History		
1/13/2017	550	DRILLING AUTHORITY ISSUED
Action Comment: TNV		
1/11/2017	155	NOI RECEIVED FOR A NEW NON-PRODUCTION WELL
Action Comment: TNV		

ARIZONA DEPARTMENT OF WATER RESOURCES
1110 W. Washington St. Suite 310
Phoenix, Arizona 85007

THIS AUTHORIZATION SHALL BE IN POSSESSION OF THE DRILLER DURING ALL DRILLING OPERATIONS

WELL REGISTRATION NO: 55-226797

AUTHORIZED DRILLER: **NATIONAL EWP, INC.**

LICENSE NO: 823

NOTICE OF INTENTION TO DRILL ENV - MONITOR WELL(S) HAS BEEN FILED WITH THE DEPARTMENT BY:

WELL OWNER: **FLORENCE COPPER, INC. 1575 W. HUNT HWY FLORENCE, AZ, 85132**

THE WELL(S) IS/ARE TO BE LOCATED IN THE:

SE 1/4 of the NW 1/4 of the SW 1/4 Section 28 Township 4.0 SOUTH Range 9.0 EAST

NO. OF WELLS IN THIS PROJECT: 1

THIS AUTHORIZATION EXPIRES AT MIDNIGHT ON THE DAY OF **January 11, 2018**

Sella Munillo

GROUNDWATER PERMITTING AND WELLS

THE DRILLER MUST FILE A LOG OF THE WELL WITHIN 30 DAYS OF COMPLETION OF DRILLING.



ARIZONA DEPARTMENT of WATER RESOURCES
1110 W. Washington St. Suite 310
Phoenix, AZ 85007
602-771-8500
azwater.gov

January 13, 2017

FLORENCE COPPER, INC.
1575 W. HUNT HWY
FLORENCE, AZ 85132



DOUGLAS A. DUCEY
Governor

THOMAS BUSCHATZKE
Director

Registration No. 55- 226797
File Number: D(4-9) 28 CBD

Dear Well Applicant:

Enclosed is a copy of the Notice of Intention to Drill (NOI) a well which you or your driller recently filed with the Department of Water Resources. This letter is to inform you that the Department has approved the NOI and has mailed, or made available for download, a drilling authorization card to your designated well drilling contractor. The driller may not begin drilling until he/she has received the authorization, and must keep it in their possession at the well site during drilling. Although the issuance of this drill card authorizes you to drill the proposed well under state law, the drilling of the well may be subject to restrictions or regulations imposed by other entities.

Well drilling activities must be completed within one year after the date the NOI was filed with the Department. If drilling is not completed within one year, a new NOI must be filed and authorization from this Department received before proceeding with drilling. If the well cannot be successfully completed as initially intended (dry hole, cave in, lost tools, etc.), the well must be properly abandoned and a Well Abandonment Completion Report must be filed by your driller [as required by A.A.C. R12-15-816(F)].

If you change drillers, you must notify the Department of the new driller's identity on a Request to Change Well Information (form 55-71A). Please ensure that the new driller is licensed by the Department to drill the type of well you require. A new driller may not begin drilling until he/she receives a new drilling authorization card from the Department.

If you find it necessary to change the location of the proposed well(s), you may not proceed with drilling until you file an amended NOI with the Department. An amended drilling authorization card will then be issued to the well drilling contractor, which must be in their possession before drilling begins.

Arizona statute [A.R.S. § 45-600] requires registered well owners to file a Pump Installation Completion Report (form 55-56) with the Department within 30 days after the installation of pumping equipment, if authorized. A blank report is enclosed for your convenience. State statute also requires the driller to file a complete and accurate Well Drillers Report and Well Log (form 55-55) within 30 days after completion of drilling. A blank report form was provided to your driller with the drilling authorization card. You should insist and ensure that all of the required reports are accurately completed and timely filed with the Department.

Please be advised that Arizona statute [A.R.S. § 45-593(C)] requires a registered well owner to notify the Department of a change in ownership of the well and/or information pertaining to the physical characteristics of the well in order to keep this well registration file current and accurate. Any change in well information or a request to change well driller must be filed on a Request to Change Well Information form (form 55-71A) that may be downloaded from the ADWR Internet website at www.azwater.gov.

Sincerely,

Groundwater Permitting and Wells Section



Arizona Department of Water Resources
Groundwater Permitting and Wells Section
P.O. Box 36020 Phoenix, Arizona 85067-6020
(602) 771-8500 • (602) 771-8690
• www.azwater.gov

**Notice of Intent to
Drill, Deepen, or Modify a
Monitor / Piezometer / Environmental Well**

**\$150
FEE**

- ❖ Review instructions prior to completing form in black or blue ink.
 - ❖ You must include with your Notice:
 - \$150 check or money order for the filing fee.
 - Well construction diagram, labeling all specifications listed in Section 6 and Section 7.
- Authority for fee: A.R.S. § 45-596 and A.A.C. R12-15-104.

AMA / INA <i>Pinal</i>	B <i>PIN</i>	SB <i>11</i>	FILE NUMBER <i>D14-9128 CBD</i>
RECEIVED <i>1/11/2017</i>	DATE <i>08</i>	WS <i>UGR</i>	WELL REGISTRATION NUMBER <i>55 - 226797</i>
ISSUED <i>1/13/2017</i>	DATE <i>000</i>	REMEDIAL ACTION SITE	

SECTION 1. REGISTRY INFORMATION

To determine the location of well, please refer to the Well Registry Map (<https://gisweb.azwater.gov/WellRegistry/Default.aspx>) and/or Google Earth (<http://www.earthpoint.us/Townships.aspx>)

Well Type	Proposed Action	Location of Well																		
CHECK ONE <input checked="" type="checkbox"/> Monitor <input type="checkbox"/> Piezometer <input type="checkbox"/> Vadose Zone <input type="checkbox"/> Air Sparging <input type="checkbox"/> Soil Vapor Extraction <input type="checkbox"/> Other (please specify):	CHECK ONE <input checked="" type="checkbox"/> Drill New Well <input type="checkbox"/> Deepen <input type="checkbox"/> Modify WELL REGISTRATION NUMBER (if Deepening or Modifying) 55 -	WELL LOCATION ADDRESS (IF ANY) <table border="1"> <tr> <th>TOWNSHIP(N/S)</th> <th>RANGE (E/W)</th> <th>SECTION</th> <th>160 ACRE</th> <th>40 ACRE</th> <th>10 ACRE</th> </tr> <tr> <td>4.0 S</td> <td>9.0 E</td> <td>28</td> <td>SW 1/4</td> <td>NW 1/4</td> <td>SE 1/4</td> </tr> </table> COUNTY ASSESSOR'S PARCEL ID NUMBER <table border="1"> <tr> <th>BOOK</th> <th>MAP</th> <th>PARCEL</th> </tr> <tr> <td></td> <td></td> <td>1001</td> </tr> </table> COUNTY WHERE WELL IS LOCATED PINAL	TOWNSHIP(N/S)	RANGE (E/W)	SECTION	160 ACRE	40 ACRE	10 ACRE	4.0 S	9.0 E	28	SW 1/4	NW 1/4	SE 1/4	BOOK	MAP	PARCEL			1001
TOWNSHIP(N/S)	RANGE (E/W)	SECTION	160 ACRE	40 ACRE	10 ACRE															
4.0 S	9.0 E	28	SW 1/4	NW 1/4	SE 1/4															
BOOK	MAP	PARCEL																		
		1001																		

SECTION 2. OWNER INFORMATION

Land Owner	Well Owner (check this box if Land Owner and Well Owner are same <input type="checkbox"/>)
FULL NAME OF COMPANY, ORGANIZATION, OR INDIVIDUAL AZ State Land Dept (Mineral Lease # 11-026500)	FULL NAME OF COMPANY, GOVERNMENT AGENCY, OR INDIVIDUAL Florence Copper, Inc. RECEIVED
MAILING ADDRESS 1616 W Adams St	MAILING ADDRESS 1575 W Hunt Hwy JAN 11 2017
CITY / STATE / ZIP CODE Phoenix, AZ 85007	CITY / STATE / ZIP CODE Florence, AZ 85132 ADWR
CONTACT PERSON NAME AND TITLE Lisa Atkins, State Land Commissioner	CONTACT PERSON NAME AND TITLE Ian Ream, Senior Hydrogeologist
TELEPHONE NUMBER (602) 542-4631	TELEPHONE NUMBER (520) 374-3984
FAX	FAX (520) 374-3999

SECTION 3. DRILLING AUTHORIZATION

Drilling Firm	Consultant (if applicable)
NAME National EWP	CONSULTING FIRM Haley & Aldrich, Inc.
DWR LICENSE NUMBER 823	CONTACT PERSON NAME Mark Nicholls
ROC LICENSE CATEGORY A-4	TELEPHONE NUMBER 602-760-2423
TELEPHONE NUMBER (480) 558-3590	FAX 602-760-2448
FAX 480-558-3525	EMAIL ADDRESS mnicholls@haleyaldrich.com
EMAIL ADDRESS jstephens@nationalewp.com	

SECTION 4.

Questions	Yes	No	Explanation:
1. Are all annular spaces between the casing(s) and the borehole for the placement of grout at least 2 inches?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	2-inch annular spaces are special standards required for wells located in and near groundwater contamination sites (such as CERCLA, WQARF, DOD, LUST).
2. Is the screened or perforated interval of casing greater than 100 feet in length?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	100-foot maximum screen intervals are a special standard for wells located in and near groundwater contamination sites (such as CERCLA, WQARF, DOD, LUST).
3. Are you requesting a variance to use thermoplastic casing in lieu of steel casing in the surface seal?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	The wells must be constructed in a vault. Pursuant to A.A.C. R12-15-801 (27) a "vault" is defined as a tamper-resistant watertight structure used to complete a well below the land surface.
4. Is there another well name or identification number associated with this well? (e.g., MW-1, PZ2, 05-04, etc.)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If yes, please state M55-UBF
5. Have construction plans been coordinated with the Arizona Department of Environmental Quality?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If yes, please state agency contact & phone number David Haas. 602-771-4669
6. For monitor wells, is dedicated pump equipment to be installed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If yes, please state design pump capacity (Gallons per Minute) Low-flow
7. Is this well a new well located in an Active Management Area AND intended to pump water for the purpose of remediating groundwater?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	You must also file a supplemental form A.R.S. § 45-454(c) & (f) unless the well is a replacement well and the total number of operable wells on the site is not increasing. (See instructions)
8. Will the well registration number be stamped on the vault cover or on the upper part of the casing?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	If no, where will the registration number be placed?

Notice of Intent to Drill, Deepen, or Modify a Monitor / Piezometer / Environmental Well

WELL REGISTRATION NUMBER
55 - 226797

SECTION 6. WELL CONSTRUCTION DETAILS

Drill Method	Method of Well Development	Grout Emplacement Method
CHECK ONE <input type="checkbox"/> Air Rotary <input type="checkbox"/> Bored or Augered <input type="checkbox"/> Cable Tool <input type="checkbox"/> Dual Rotary <input checked="" type="checkbox"/> Mud Rotary <input type="checkbox"/> Reverse Circulation <input type="checkbox"/> Driven <input type="checkbox"/> Jetted <input type="checkbox"/> Air Percussion / Odex Tubing <input type="checkbox"/> Other (please specify):	CHECK ONE <input checked="" type="checkbox"/> Airlift <input type="checkbox"/> Bail <input type="checkbox"/> Surge Block <input type="checkbox"/> Surge Pump <input type="checkbox"/> Other (please specify):	CHECK ONE <input checked="" type="checkbox"/> Tremie Pumped (Recommended) <input type="checkbox"/> Gravity <input type="checkbox"/> Pressure Grout <input type="checkbox"/> Other (please specify):
	Method of Sealing at Reduction Points	Surface or Conductor Casing
DATE CONSTRUCTION TO BEGIN 01/16/2017	CHECK ONE <input checked="" type="checkbox"/> None <input type="checkbox"/> Welded <input type="checkbox"/> Swedged <input type="checkbox"/> Packed <input type="checkbox"/> Other (please specify):	CHECK ONE <input type="checkbox"/> Flush Mount in a vault <input checked="" type="checkbox"/> Extends at least 1' above grade

SECTION 7. PROPOSED WELL CONSTRUCTION PLAN (attach additional page if needed)

Attach a well construction diagram labeling all specifications below.

Borehole			Casing													
DEPTH FROM SURFACE		BOREHOLE DIAMETER (inches)	DEPTH FROM SURFACE		OUTER DIAMETER (inches)	MATERIAL TYPE (T)				PERFORATION TYPE (T)					SLOT SIZE IF ANY (inches)	
FROM (feet)	TO (feet)		FROM (feet)	TO (feet)		STEEL	PVC	ABS	IF OTHER TYPE, DESCRIBE	BLANK OR NONE	WIRE WRAP	SHUTTER SCREEN	MILLS KNIFE	SLOTTED		IF OTHER TYPE, DESCRIBE
0	20	14	0	20	14	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
20	270	10.5	0	240	5	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
			240	260	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		0.020

Annular Material

DEPTH FROM SURFACE		ANNULAR MATERIAL TYPE (T)								FILTER PACK		
FROM (feet)	TO (feet)	NONE	CONCRETE	NEAT CEMENT OR CEMENT GROUT	CEMENT-BENTONITE GROUT	BENTONITE GROUT	CHIPS	PELLETS	IF OTHER TYPE OF ANNULAR MATERIAL, DESCRIBE	SAND	GRAVEL	SIZE
0	220	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	
220	230	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	
230	270	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	No. 8-12


IF THIS WELL HAS NESTED CASINGS, SPECIFY NUMBER OF CASING STRINGS
 EXPECTED DEPTH TO WATER (Feet Below Ground Surface)
 211

SECTION 8. PERMISSION TO ACCESS

☐ By checking this box, I hereby provide ADWR permission to enter the property for the purpose of taking water level measurements at this well. (See instructions.)

SECTION 9. LAND OWNER AND WELL OWNER SIGNATURE

I state that this notice is filed in compliance with A.R.S. § 45-596 and is complete and correct to the best of my knowledge and


Land Owner	Well Owner (if different from Land Owner, See instructions)
PRINT NAME AND TITLE	PRINT NAME AND TITLE Ian Ream, Senior Hydrogeologist
SIGNATURE OF LAND OWNER	SIGNATURE OF WELL OWNER 
DATE	DATE Jan 9, 2017
<input type="checkbox"/> By checking this box, you agree to allow ADWR to contact you via electronic mail.	<input checked="" type="checkbox"/> By checking this box, you agree to allow ADWR to contact you via electronic mail.
EMAIL ADDRESS	EMAIL ADDRESS IanReam@florencecopper.com

SECTION 5. Well Construction Diagram

Provide a well construction diagram showing all existing well construction features listed in Section 6 and Section 7.

See attached well diagram.

SS-226797



MOBINI, GITA
 G:\PROJECTS\CURIS RESOURCES\338706-CURIS FEASIBILITY\DRAWINGS\M55-UBF WELL DESIGN.DWG
 Printed: 6/26/2015 2:16 PM Layout: M55-UBF




FLORENCE COPPER, INC.
 FLORENCE, ARIZONA


**M55-UBF
 WELL CONSTRUCTION DIAGRAM**



SCALE: NOT TO SCALE

FIGURE 1





20

200310240

21

20031018E

20031018N

22

21101010A

20031054B

USA200060

PINAL AMA

200310450

200310470

20035007

20031054A

28

20035002B

27

29

T 4S
R 9E

ARIZONA

20035003

20031019E

20035006A

200310200

200370010

20038001A

32

33

20038001B

20031019C

34

20037013A

200380020

20031019D

20031019D

20031019D

Torren Valdez

From: Ian Ream <IanReam@florencecopper.com>
Sent: Friday, January 13, 2017 9:06 AM
To: Torren Valdez
Subject: Re: Map of monitor well locations

Hi Torren,

The pumps will be QED micro purge. They typically do a liter or two a minute. Very low flow. Looking for discreet interval samples. The flow rate is based on drawdown. The goal is not to draw down the well much more than a half a foot or 1 foot.

Thanks,

Ian Ream
Senior Hydrogeologist
Florence Copper

On Jan 13, 2017, at 8:56 AM, Torren Valdez <tvaldez@azwater.gov> wrote:

Ian,

Would you happen to know the pump capacity (gpm) for the low-flow pumps that will be installed on those monitoring wells?

Thank you,

Torren Valdez
Water Planning & Permitting Division
Arizona Department of Water Resources
602.771.8614

<image002.jpg>

From: Ian Ream [<mailto:IanReam@florencecopper.com>]
Sent: Thursday, January 12, 2017 11:13 AM
To: Torren Valdez <tvaldez@azwater.gov>
Subject: Map of monitor well locations

Hi Torren,

Here is a map with the well locations.

Please don't hesitate to contact me if you need anything else or have any questions.

Cheers,

Ian

Ian Ream Senior Hydrogeologist

<image003.jpg>

Florence Copper Inc.

1575 W. Hunt Highway Florence AZ USA 85132

C 520-840-9604 T 520-374-3984 F 520-374-3999

E ianream@florencecopper.com Web florencecopper.com

"Notice Regarding Transmission

This message is intended only for the person(s) to whom it is addressed and may contain information that is privileged and confidential. If you are not the intended recipient, you are hereby notified that any dissemination or copying of this communication is prohibited. Please notify us of the error in communication by telephone (778-373-4533) or by return e-mail and destroy all copies of this communication. Please note that any views or opinions presented in this email are solely those of the author and do not necessarily represent those of Taseko Mines Limited or any affiliated or associated company. The recipient should check this email and any attachments for the presence of viruses. Neither Taseko Mines Limited nor any affiliated or associated company accepts any liability for any damage caused by any virus transmitted by this email. Thank you."

"Notice Regarding Transmission

This message is intended only for the person(s) to whom it is addressed and may contain information that is privileged and confidential. If you are not the intended recipient, you are hereby notified that any dissemination or copying of this communication is prohibited. Please notify us of the error in communication by telephone (778-373-4533) or by return e-mail and destroy all copies of this communication. Please note that any views or opinions presented in this email are solely those of the author and do not necessarily represent those of Taseko Mines Limited or any affiliated or associated company. The recipient should check this email and any attachments for the presence of viruses. Neither Taseko Mines Limited nor any affiliated or associated company accepts any liability for any damage caused by any virus transmitted by this email. Thank you."

NOTICE

A.R.S. § 41-1030(B), (D), (E) and (F) provide as follows:

B. An agency shall not base a licensing decision in whole or in part on a licensing requirement or condition that is not specifically authorized by statute, rule or state tribal gaming compact. A general grant of authority in statute does not constitute a basis for imposing a licensing requirement or condition unless a rule is made pursuant to that general grant of authority that specifically authorizes the requirement or condition.

D. This section may be enforced in a private civil action and relief may be awarded against the state. The court may award reasonable attorney fees, damages and all fees associated with the license application to a party that prevails in an action against the state for a violation of this section.

E. A state employee may not intentionally or knowingly violate this section. A violation of this section is cause for disciplinary action or dismissal pursuant to the agency's adopted personnel policy.

F. This section does not abrogate the immunity provided by section 12-820.01 or 12-820.02.

ARIZONA DEPARTMENT of WATER RESOURCES
1110 W. Washington St. Suite 310
Engineering and Permits Division
Phoenix, AZ 85007
602-771-8500

NOTICE TO WELL DRILLERS

This is a reminder that a valid drill card be present for the drilling of each and every well constructed on a site.* The problem seems to occur during the construction of a well when an unexpected problem occurs. Either the hole collapses, the hole is dry, a drill bit is lost and can't be recovered, or any number of other situations where the driller feels that he needs to move over and start another well. If you encounter this type of scenario, please be aware drillers do not have the authority to start another well without first obtaining drilling authority for the new well. Please note the following statutes and regulations pertaining to well drilling and construction:

ARIZONA REVISED STATUTE (A.R.S.)

A.R.S. § 45-592.A.

A person may construct, replace or deepen a well in this state only pursuant to this article and section 45-834.01. The drilling of a well may not begin until all requirements of this article and section 45-834.01, as applicable, are met.

A.R.S. § 594.A.

The director shall adopt rules establishing construction standards for new wells and replacement wells, the deepening and abandonment of existing wells and the capping of open wells.

A.R.S. § 600.A

A well driller shall maintain a complete and accurate log of each well drilled.

ARIZONA ADMINISTRATIVE CODE (A.A.C.)

A.A.C. R12-15-803.A.

A person shall not drill or abandon a well, or cause a well to be drilled or abandoned, in a manner which is not in compliance with A.R.S. Title 45, Chapter 2, Article 10, and the rules adopted thereunder.

A.A.C. R12-15-810.A.

A well drilling contractor or single well licensee may commence drilling a well only if the well drilling contractor or licensee has possession of a drilling card at the well site issued by the Director in the name of the well drilling contractor or licensee, authorizing the drilling of the specific well in the specific location.

A.A.C. R12-15-816.F.

In the course of drilling a new well, the well may be abandoned without first filing a notice of intent to abandon and without an abandonment card.

*** THIS REQUIREMENT DOES NOT PERTAIN TO THE DRILLING OF MINERAL EXPLORATION, GEOTECHNICAL OR HEAT PUMP BOREHOLES**

Transaction Receipt - Success

Arizona Water Resources
Arizona Water Resources
MID:347501639533
1700 W Washington St
Phoenix , AZ 85012
602-771-8454

01/11/2017 04:20PM
Remittance ID
Arizona011117181536095Ald
Transaction ID:
178069995

KELSEY SHERRARD
500 Maint St
WOODLAND, California 95695
United States
Visa - 3420
Approval Code: 040691

Sale
Amount: \$1,800.00

55-226788, 55-226789, 55-226790, 55-226791, 55-226792, 55-226793, 55-226794, 55-226795, 55-226796, 55-226797, 55-226798, 55-226799


N/A

Cash Reciepts

0

palder@azwater.gov

Cardmember acknowledges
receipt of goods and/or
services in the amount of
the total shown hereon and
agrees to perform the
obligations set forth by the
cardmember's agreement with
the issuer.

Signature 
[click here](#) to continue.

Arizona Department of Water Resources

1110 West Washington Street, Suite 310

Phoenix AZ 85007

Customer:

KELSEY SHERRARD
500 MAIN STREET
WOODLAND, CA 95695

Receipt #: 17-49315
Office: MAIN OFFICE
Receipt Date: 01/11/2017
Sale Type: Mail
Cashier: WRPXA

Item No.	Function Code	AOBJ	Description	Ref ID	Qty	Unit Price	Ext Price
8505	122221	4439-6F	MONITOR, PIEZOMETER, AIR SPARGING, SOIL VAPOR EXTR		12	150.00	1,800.00
RECEIPT TOTAL:							1,800.00

Payment type: CREDIT CARD

Amount Paid: \$1,800.00

Authorization 178069995

Payment Received Date: 01/11/2017

Notes: Credit card payment for \$1,800.00 is for well registration numbers 55-226788, 55-226789, 55-226790, 55-226791, 55-226792, 55-226793, 55-226794, 55-226795, 55-226796, 55-226797, 55-226798, 55-226799

APPENDIX B

Lithologic Log

Oct 3, 17

H&A-SONIC-129687-ELEVATION HA-LIB09 WITH COMMENTS GLB HA-DIRECT PUSH + SONIC LOG.GDT G:\PROJECTS\CURIS RESOURCES\129687 MONITOR WELL DRILLING\PROJECT DATA\GINT\GINT FILES\FCI WELLS.GPJ

HALEY ALDRICH		LITHOLOGIC LOG				M55-UBF					
Project Production Test Facility Client Florence Copper, Inc. Contractor National EWP, Inc.					Cadastral Location D (4-9) 28 CBD						
Drilling Method		Conventional Mud Rotary		Concrete Pad		1478.00	feet, amsl	Start	April 10, 2017		
Borehole Diameter(s)		10.625		Datum		State Plane NAD 83		Finish	April 12, 2017		
Rig Make & Model		Schramm T685WS		Location		N 746,294 E 847,615		H&A Rep.	C. Giusti		
Elevation (ft)	Depth (ft)	Well Diagram	USCS Symbol	Stratum Change Depth (ft)	LITHOLOGY IDENTIFICATION AND DESCRIPTION				COMMENTS		
	0		SP		POORLY GRADED SAND (0-20 feet) Primarily fine sand to 2 mm with trace fines. Sand is subangular to subrounded. The color is red brown. UBFU				Well Registry ID: 55-226797		
1460	20		SW	20	WELL GRADED SAND (20-40 feet) Primarily fine to medium sand to 3 mm with trace fines. Sand is angular to subangular. The color is red gray. UBFU				Surface Completion: Locking Well Vault & Concrete Pad		
1440	40		SW	40	WELL GRADED SAND (40-60 feet) Primarily fine to coarse sand with trace fines and ~5% gravel to 10 mm. Sand and gravel is subangular to subrounded. The color is red brown. UBFU				Well casing stickup: 1.3 feet als		
1420	60		SM	60	SILTY SAND (60-80 feet) Primarily fine sand to 4 mm with ~20% fines. Sand is subangular to subrounded. Fines have low plasticity, low toughness, high dilatancy, low dry strength, and are red brown. UBFU				Unit Intervals: UBFU: 0 - 272 feet		
1400	80		SP	80	POORLY GRADED SAND (80-95 feet) Primarily fine to medium sand with trace fines and trace gravel to 8 mm. Sand and gravel is subangular to subrounded. The color is red brown. UBFU				Surface Casing: 14-inch mild steel; 0 - 40 feet		
1380	100		SP-SC	95	POORLY GRADED SAND with CLAY (95-110 feet) Primarily fine sand with ~10% fines and trace gravel to 5 mm. Sand and gravel is subangular to subrounded. Fines have medium plasticity, low toughness, no dilatancy, medium to high dry strength, and are red brown. UBFU				Well Casing: Nominal 5-inch diameter Mild Steel; 0 - 240 feet		
1360	120		SW	110	WELL GRADED SAND (110-120 feet) Primarily fine to coarse sand with trace fines and ~5% gravel to 8 mm. Sand and gravel is subangular to subrounded. The color is red brown. UBFU				Seal: Type V neat cement; 0 - 216 feet		
1340	140		SC	120	CLAYEY SAND (120-165 feet) Primarily fine sand with ~20% fines and trace gravel to 9 mm. Sand is subrounded to subangular, gravel is rounded. Fines have medium plasticity, low toughness, no dilatancy, medium dry strength, and are red brown. UBFU				Fine Sand & Bentonite; 216 - 230 feet		
1320	160		SP	165	POORLY GRADED SAND (165-185 feet) Primarily fine to medium sand with ~5% fines and ~5% gravel to 9 mm. Sand is subrounded to subangular, gravel is subrounded. Fines have medium plasticity, low toughness, no dilatancy, low dry strength, and are red brown. UBFU				Filter Pack: 8 - 12 CO Silica Sand; 230 - 272 feet		
1300	180		SW	185	WELL GRADED SAND (185-230 feet) Primarily fine to coarse sand with trace fines and ~5% gravel to 10 mm. Sand subrounded to subangular, gravel is subrounded to rounded. The color is red brown. UBFU						
1280	200										
1260	220										
1240	240		SP-SC	230	POORLY GRADED SAND with CLAY (230-235 feet) Primarily fine to medium sand with ~10% fines and ~5% gravel to 8 mm. Sand is subrounded to subangular, gravel is subrounded to rounded. Fines have medium plasticity, low toughness, low toughness, and are red brown. UBFU				Thread Adapter: Stainless Steel, SCH 80 F480 PVC to SCH 40 F480 Mild Steel: 240 feet		
1220	260		SW	245	WELL GRADED SAND (235-245 feet) Primarily fine to coarse sand with ~5% fines and ~5% gravel to 14 mm. Sand is subrounded to subangular, gravel is subrounded to rounded. Fines are nonplastic and are red brown. UBFU				Well Screen: Nominal 5-inch diameter, SCH 80 PVC Screen (0.020-inch slots); 240 - 260 feet		
			SW	250	POORLY GRADED SAND with CLAY (245-250 feet) Primarily fine to medium sand with ~10% fines and ~5% gravel to 8 mm. Sand is subrounded to subangular, gravel is subrounded to rounded. Fines have medium plasticity, low toughness, and are red brown. UBFU				Total Depth: Driller Depth = 272 feet; Geophysical Logging Depth = 272 feet		
				272	WELL GRADED SAND (250-272 feet) Primarily fine to coarse sand with ~5% fines and ~5% gravel to 14 mm. Sand is subrounded to subangular, gravel is subrounded to rounded. Fines are nonplastic and are red brown. UBFU						
NOTE: Lithologic descriptions, group symbols, and grain-size determinations based on the USCS visual-manual method (Haley & Aldrich OP2001A - Field Practice for Soil Identification and Description).											
										Sheet No. 1 of 1	

NOTE: Lithologic descriptions, group symbols, and grain-size determinations based on the USCS visual-manual method (Haley & Aldrich OP2001A - Field Practice for Soil Identification and Description).

Sheet No. 1 of 1

APPENDIX C

Chemical Characterization of Formation Water



May 23, 2018

Barbara Sylvester
Brown & Caldwell
201 E. Washington Suite 500
Phoenix, AZ 85004

TEL (602) 567-3894
FAX -

Work Order No.: 18D0619
Order Name: Florence Copper

RE: PTF

Dear Barbara Sylvester,

Turner Laboratories, Inc. received 2 sample(s) on 04/25/2018 for the analyses presented in the following report.

All results are intended to be considered in their entirety, and Turner Laboratories, Inc. is not responsible for use of less than the complete report. Results apply only to the samples analyzed. Samples will be disposed of 30 days after issue of our report unless special arrangements are made.

The pages that follow may contain sensitive, privileged or confidential information intended solely for the addressee named above. If you receive this message and are not the agent or employee of the addressee, this communication has been sent in error. Please do not disseminate or copy any of the attached and notify the sender immediately by telephone. Please also return the attached sheet(s) to the sender by mail.

Please call if you have any questions.

Respectfully submitted,

Turner Laboratories, Inc.
ADHS License AZ0066

Kevin Brim
Project Manager

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

Order: Florence Copper

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Matrix	Collection Date/Time
18D0619-01	R-09	Ground Water	04/23/2018 1555
18D0619-02	TB	Ground Water	04/25/2018 0000

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

Case Narrative

The 8015D analysis was performed by TestAmerica Laboratories, Inc. in Phoenix, AZ.

The radiochemistry analysis was performed by Radiation Safety Engineering, Inc. in Chandler, AZ.

D5 Minimum Reporting Limit (MRL) is adjusted due to sample dilution; analyte was non-detect in the sample.

H5 This test is specified to be performed in the field within 15 minutes of sampling; sample was received and analyzed past the regulatory holding time.

M3 The spike recovery value is unusable since the analyte concentration in the sample is disproportionate to the spike level. The associated LCS/LCSD recovery was acceptable.

All soil, sludge, and solid matrix determinations are reported on a wet weight basis unless otherwise noted.

ND Not Detected at or above the PQL

PQL Practical Quantitation Limit

DF Dilution Factor

PRL Project Reporting Limit

Client:	Brown & Caldwell	Client Sample ID:	R-09
Project:	PTF	Collection Date/Time:	04/23/2018 1555
Work Order:	18D0619	Matrix:	Ground Water
Lab Sample ID:	18D0619-01	Order Name:	Florence Copper

Analyses	Result	PRL	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
ICP Dissolved Metals-E 200.7 (4.4)									
Calcium	140		4.0	M3	mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Iron	ND		0.30		mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Magnesium	27		3.0		mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Potassium	6.8		5.0		mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
Sodium	170		5.0	M3	mg/L	1	04/27/2018 1440	05/04/2018 1150	MH
ICP/MS Dissolved Metals-E 200.8 (5.4)									
Aluminum	ND		0.0800	D5	mg/L	2	04/27/2018 1440	05/07/2018 1139	MH
Antimony	ND		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Arsenic	0.0016		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Barium	0.071		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Beryllium	ND		0.00050	D5	mg/L	2	04/27/2018 1440	05/07/2018 1139	MH
Cadmium	ND		0.00025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Chromium	0.0051		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Cobalt	ND		0.00025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Copper	0.011		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Lead	ND		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Manganese	0.0020		0.00025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Nickel	0.0033		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Selenium	ND		0.0025		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Thallium	ND		0.00050		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
Zinc	ND		0.040		mg/L	1	04/27/2018 1440	05/07/2018 1133	MH
CVAA Dissolved Mercury-E 245.1									
Mercury	ND		0.0010		mg/L	1	04/26/2018 0955	04/26/2018 1639	MH
pH-E150.1									
pH (pH Units)	7.8			H5	-	1	04/26/2018 1615	04/26/2018 1616	AP
Temperature (°C)	22			H5	-	1	04/26/2018 1615	04/26/2018 1616	AP
ICP/MS Total Metals-E200.8 (5.4)									
Uranium	0.016		0.00050		mg/L	1	04/27/2018 1230	04/30/2018 1348	MH

Client: Brown & Caldwell

Project: PTF

Work Order: 18D0619

Lab Sample ID: 18D0619-01

Client Sample ID: R-09

Collection Date/Time: 04/23/2018 1555

Matrix: Ground Water

Order Name: Florence Copper

Analyses	Result	PRL	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
Anions by Ion Chromatography-E300.0 (2.1)									
Chloride	310		25		mg/L	25	04/26/2018 1225	04/26/2018 1415	AP
Fluoride	ND		0.50		mg/L	1	04/25/2018 1208	04/25/2018 1544	AP
Nitrogen, Nitrate (As N)	8.8		0.50		mg/L	1	04/25/2018 1208	04/25/2018 1544	AP
Nitrogen, Nitrite (As N)	ND		0.10		mg/L	1	04/25/2018 1208	04/25/2018 1544	AP
Sulfate	190		130		mg/L	25	04/26/2018 1225	04/26/2018 1415	AP
Cyanide-E335.4									
Cyanide	ND		0.10		mg/L	1	04/26/2018 0845	04/30/2018 1545	AP
Alkalinity-SM2320B									
Alkalinity, Bicarbonate (As CaCO3)	150		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Carbonate (As CaCO3)	ND		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Hydroxide (As CaCO3)	ND		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Phenolphthalein (As CaCO3)	ND		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Alkalinity, Total (As CaCO3)	150		2.0		mg/L	1	05/03/2018 1030	05/03/2018 1210	EJ
Specific Conductance-SM2510 B									
Conductivity	1700		0.20		µmhos/cm	2	05/09/2018 1315	05/09/2018 1330	AP
Total Dissolved Solids (Residue, Filterable)-SM2540 C									
Total Dissolved Solids (Residue, Filterable)	1000		20		mg/L	1	04/26/2018 0826	05/01/2018 1600	EJ
Volatile Organic Compounds by GC/MS-SW8260B									
Benzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Carbon disulfide	ND		2.0		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Ethylbenzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Toluene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Xylenes, Total	ND		1.5		ug/L	1	05/07/2018 1824	05/07/2018 1943	KP
Surr: 4-Bromofluorobenzene	95	70-130			%REC	1	05/07/2018 1824	05/07/2018 1943	KP
Surr: Dibromofluoromethane	101	70-130			%REC	1	05/07/2018 1824	05/07/2018 1943	KP
Surr: Toluene-d8	77	70-130			%REC	1	05/07/2018 1824	05/07/2018 1943	KP

Client: Brown & Caldwell

Project: PTF

Work Order: 18D0619

Lab Sample ID: 18D0619-02

Client Sample ID: TB

Collection Date/Time: 04/25/2018 0000

Matrix: Ground Water

Order Name: Florence Copper

Analyses	Result	PRL	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
Volatile Organic Compounds by GC/MS-SW8260B									
Benzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Carbon disulfide	ND		2.0		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Ethylbenzene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Toluene	ND		0.50		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Xylenes, Total	ND		1.5		ug/L	1	05/07/2018 1824	05/07/2018 2344	KP
Surr: 4-Bromofluorobenzene	101	70-130			%REC	1	05/07/2018 1824	05/07/2018 2344	KP
Surr: Dibromofluoromethane	110	70-130			%REC	1	05/07/2018 1824	05/07/2018 2344	KP
Surr: Toluene-d8	103	70-130			%REC	1	05/07/2018 1824	05/07/2018 2344	KP

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1804269 - E 245.1										
Blank (1804269-BLK1)				Prepared & Analyzed: 04/26/2018						
Mercury	ND	0.0010	mg/L							
LCS (1804269-BS1)				Prepared & Analyzed: 04/26/2018						
Mercury	0.0049	0.0010	mg/L	0.005000		98	85-115			
LCS Dup (1804269-BSD1)				Prepared & Analyzed: 04/26/2018						
Mercury	0.0048	0.0010	mg/L	0.005000		95	85-115	2	20	
Matrix Spike (1804269-MS1)				Source: 18D0394-01			Prepared & Analyzed: 04/26/2018			
Mercury	0.0050	0.0010	mg/L	0.005000	0.00020	97	85-115			
Matrix Spike Dup (1804269-MSD1)				Source: 18D0394-01			Prepared & Analyzed: 04/26/2018			
Mercury	0.0050	0.0010	mg/L	0.005000	0.00020	96	85-115	1	20	
Batch 1804292 - E200.8 (5.4)										
Blank (1804292-BLK1)				Prepared & Analyzed: 04/30/2018						
Uranium	ND	0.00050	mg/L							
LCS (1804292-BS1)				Prepared & Analyzed: 04/30/2018						
Uranium	0.046	0.00050	mg/L	0.05000		92	85-115			
LCS Dup (1804292-BSD1)				Prepared & Analyzed: 04/30/2018						
Uranium	0.046	0.00050	mg/L	0.05000		92	85-115	0.2	20	
Matrix Spike (1804292-MS1)				Source: 18D0614-01			Prepared & Analyzed: 04/30/2018			
Uranium	0.051	0.00050	mg/L	0.05000	0.0015	99	70-130			
Batch 1805051 - E 200.7 (4.4)										
Blank (1805051-BLK1)				Prepared & Analyzed: 05/04/2018						
Calcium	ND	4.0	mg/L							
Iron	ND	0.30	mg/L							
Magnesium	ND	3.0	mg/L							
Potassium	ND	5.0	mg/L							
Sodium	ND	5.0	mg/L							
LCS (1805051-BS1)				Prepared & Analyzed: 05/04/2018						
Calcium	11	4.0	mg/L	10.00		109	85-115			
Iron	1.0	0.30	mg/L	1.000		104	85-115			
Magnesium	10	3.0	mg/L	10.00		105	85-115			
Potassium	10	5.0	mg/L	10.00		105	85-115			
Sodium	10	5.0	mg/L	10.00		105	85-115			
LCS Dup (1805051-BSD1)				Prepared & Analyzed: 05/04/2018						
Calcium	11	4.0	mg/L	10.00		110	85-115	1	20	
Iron	1.0	0.30	mg/L	1.000		105	85-115	0.5	20	
Magnesium	10	3.0	mg/L	10.00		105	85-115	0.06	20	
Potassium	10	5.0	mg/L	10.00		105	85-115	0.05	20	
Sodium	11	5.0	mg/L	10.00		109	85-115	4	20	

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1805051 - E 200.7 (4.4)										
Matrix Spike (1805051-MS1)		Source: 18D0619-01		Prepared & Analyzed: 05/04/2018						
Calcium	150	4.0	mg/L	10.00	140	59	70-130			M3
Iron	1.1	0.30	mg/L	1.000	0.028	105	70-130			
Magnesium	38	3.0	mg/L	10.00	27	108	70-130			
Potassium	17	5.0	mg/L	10.00	6.8	105	70-130			
Sodium	170	5.0	mg/L	10.00	170	30	70-130			M3
Matrix Spike (1805051-MS2)		Source: 18E0021-01		Prepared & Analyzed: 05/04/2018						
Calcium	64	4.0	mg/L	10.00	54	103	70-130			
Iron	1.0	0.30	mg/L	1.000	0.0060	101	70-130			
Magnesium	21	3.0	mg/L	10.00	11	99	70-130			
Potassium	15	5.0	mg/L	10.00	4.7	104	70-130			
Sodium	99	5.0	mg/L	10.00	90	87	70-130			
Batch 1805069 - E 200.8 (5.4)										
Blank (1805069-BLK1)		Prepared & Analyzed: 05/07/2018								
Aluminum	ND	0.0400	mg/L							
Antimony	ND	0.00050	mg/L							
Arsenic	ND	0.00050	mg/L							
Barium	ND	0.00050	mg/L							
Beryllium	ND	0.00025	mg/L							
Cadmium	ND	0.00025	mg/L							
Chromium	ND	0.00050	mg/L							
Cobalt	ND	0.00025	mg/L							
Copper	ND	0.00050	mg/L							
Lead	ND	0.00050	mg/L							
Manganese	ND	0.00025	mg/L							
Nickel	ND	0.00050	mg/L							
Selenium	ND	0.0025	mg/L							
Thallium	ND	0.00050	mg/L							
Zinc	ND	0.040	mg/L							
LCS (1805069-BS1)		Prepared & Analyzed: 05/07/2018								
Aluminum	0.104	0.0400	mg/L	0.1000		104	85-115			
Antimony	0.048	0.00050	mg/L	0.05000		96	85-115			
Arsenic	0.050	0.00050	mg/L	0.05000		100	85-115			
Barium	0.050	0.00050	mg/L	0.05000		100	85-115			
Beryllium	0.049	0.00025	mg/L	0.05000		97	85-115			
Cadmium	0.050	0.00025	mg/L	0.05000		100	85-115			
Chromium	0.051	0.00050	mg/L	0.05000		102	85-115			
Cobalt	0.051	0.00025	mg/L	0.05000		101	85-115			
Copper	0.051	0.00050	mg/L	0.05000		103	85-115			
Lead	0.049	0.00050	mg/L	0.05000		98	85-115			
Manganese	0.050	0.00025	mg/L	0.05000		101	85-115			
Nickel	0.051	0.00050	mg/L	0.05000		102	85-115			
Selenium	0.051	0.0025	mg/L	0.05000		103	85-115			
Thallium	0.050	0.00050	mg/L	0.05000		101	85-115			
Zinc	0.10	0.040	mg/L	0.1000		101	85-115			

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1805069 - E 200.8 (5.4)										
LCS Dup (1805069-BSD1)				Prepared & Analyzed: 05/07/2018						
Aluminum	0.115	0.0400	mg/L	0.1000		115	85-115	10	20	
Antimony	0.048	0.00050	mg/L	0.05000		96	85-115	0.7	20	
Arsenic	0.050	0.00050	mg/L	0.05000		101	85-115	0.8	20	
Barium	0.051	0.00050	mg/L	0.05000		102	85-115	1	20	
Beryllium	0.049	0.00025	mg/L	0.05000		97	85-115	0.2	20	
Cadmium	0.050	0.00025	mg/L	0.05000		100	85-115	0.2	20	
Chromium	0.051	0.00050	mg/L	0.05000		102	85-115	0.4	20	
Cobalt	0.050	0.00025	mg/L	0.05000		101	85-115	0.5	20	
Copper	0.052	0.00050	mg/L	0.05000		105	85-115	2	20	
Lead	0.049	0.00050	mg/L	0.05000		98	85-115	0.1	20	
Manganese	0.050	0.00025	mg/L	0.05000		101	85-115	0.09	20	
Nickel	0.051	0.00050	mg/L	0.05000		103	85-115	0.8	20	
Selenium	0.052	0.0025	mg/L	0.05000		104	85-115	2	20	
Thallium	0.050	0.00050	mg/L	0.05000		101	85-115	0.06	20	
Zinc	0.10	0.040	mg/L	0.1000		104	85-115	3	20	
Matrix Spike (1805069-MS1)				Source: 18D0693-01	Prepared & Analyzed: 05/07/2018					
Aluminum	0.239	0.0400	mg/L	0.1000	0.166	74	70-130			
Antimony	0.045	0.00050	mg/L	0.05000	0.00024	90	70-130			
Arsenic	0.056	0.00050	mg/L	0.05000	0.0035	104	70-130			
Barium	0.16	0.00050	mg/L	0.05000	0.12	94	70-130			
Beryllium	0.045	0.00025	mg/L	0.05000	0.000029	90	70-130			
Cadmium	0.047	0.00025	mg/L	0.05000	ND	94	70-130			
Chromium	0.049	0.00050	mg/L	0.05000	0.00052	98	70-130			
Cobalt	0.048	0.00025	mg/L	0.05000	0.00097	95	70-130			
Copper	0.051	0.00050	mg/L	0.05000	0.0020	98	70-130			
Lead	0.047	0.00050	mg/L	0.05000	0.00016	94	70-130			
Manganese	0.054	0.00025	mg/L	0.05000	0.0075	94	70-130			
Nickel	0.049	0.00050	mg/L	0.05000	0.0018	94	70-130			
Selenium	0.057	0.0025	mg/L	0.05000	ND	114	70-130			
Thallium	0.048	0.00050	mg/L	0.05000	0.000038	96	70-130			
Zinc	0.11	0.040	mg/L	0.1000	ND	109	70-130			

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1804261 - SM2540 C										
Duplicate (1804261-DUP1)		Source: 18D0606-01		Prepared: 04/26/2018 Analyzed: 04/27/2018						
Total Dissolved Solids (Residue, Filterable)	630	20	mg/L		630			0.3	5	
Duplicate (1804261-DUP2)		Source: 18D0606-02		Prepared: 04/26/2018 Analyzed: 04/27/2018						
Total Dissolved Solids (Residue, Filterable)	610	20	mg/L		620			0.8	5	
Batch 1804268 - E335.4										
Blank (1804268-BLK1)		Prepared: 04/26/2018 Analyzed: 04/30/2018								
Cyanide	ND	0.10	mg/L							
LCS (1804268-BS1)		Prepared: 04/26/2018 Analyzed: 04/30/2018								
Cyanide	2.0	0.10	mg/L	2.000		101	90-110			
LCS Dup (1804268-BSD1)		Prepared: 04/26/2018 Analyzed: 04/30/2018								
Cyanide	2.0	0.10	mg/L	2.000		101	90-110	0.1	20	
Matrix Spike (1804268-MS1)		Source: 18D0602-03		Prepared: 04/26/2018 Analyzed: 04/30/2018						
Cyanide	2.1	0.10	mg/L	2.000	ND	103	90-110			
Matrix Spike Dup (1804268-MSD1)		Source: 18D0602-03		Prepared: 04/26/2018 Analyzed: 04/30/2018						
Cyanide	2.0	0.10	mg/L	2.000	ND	98	90-110	5	20	
Batch 1804272 - E150.1										
Duplicate (1804272-DUP1)		Source: 18D0662-02		Prepared & Analyzed: 04/26/2018						
pH (pH Units)	7.8		-		7.8			0.1	200	H5
Temperature (°C)	21		-		21			2	200	H5
Batch 1805027 - SM2320B										
LCS (1805027-BS1)		Prepared & Analyzed: 05/03/2018								
Alkalinity, Total (As CaCO3)	240	2.0	mg/L	250.0		96	90-110			
LCS Dup (1805027-BSD1)		Prepared & Analyzed: 05/03/2018								
Alkalinity, Total (As CaCO3)	240	2.0	mg/L	250.0		96	90-110	0	10	
Matrix Spike (1805027-MS1)		Source: 18D0606-02		Prepared & Analyzed: 05/03/2018						
Alkalinity, Total (As CaCO3)	370	2.0	mg/L	250.0	130	96	85-115			
Matrix Spike Dup (1805027-MSD1)		Source: 18D0606-02		Prepared & Analyzed: 05/03/2018						
Alkalinity, Total (As CaCO3)	370	2.0	mg/L	250.0	130	95	85-115	0.5	10	
Batch 1805103 - SM2510 B										
LCS (1805103-BS1)		Prepared & Analyzed: 05/09/2018								
Conductivity	140	0.10	µmhos/cm	141.2		101	0-200			
LCS Dup (1805103-BSD1)		Prepared & Analyzed: 05/09/2018								
Conductivity	140	0.10	µmhos/cm	141.2		101	0-200	0.7	200	
Duplicate (1805103-DUP1)		Source: 18E0192-01		Prepared & Analyzed: 05/09/2018						
Conductivity	4.0	0.10	µmhos/cm		4.0			0	10	

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018


QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1805074 - SW8260B										
Blank (1805074-BLK1)				Prepared & Analyzed: 05/07/2018						
Benzene	ND	0.50	ug/L							
Carbon disulfide	ND	2.0	ug/L							
Ethylbenzene	ND	0.50	ug/L							
Toluene	ND	0.50	ug/L							
Xylenes, Total	ND	1.5	ug/L							
Surrogate: 4-Bromofluorobenzene	25.0		ug/L	25.00		100	70-130			
Surrogate: Dibromofluoromethane	26.9		ug/L	25.00		107	70-130			
Surrogate: Toluene-d8	25.1		ug/L	25.00		100	70-130			
LCS (1805074-BS1)				Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	29		ug/L	25.00		114	70-130			
Benzene	27		ug/L	25.00		109	70-130			
Chlorobenzene	29		ug/L	25.00		115	70-130			
Toluene	25		ug/L	25.00		101	70-130			
Trichloroethene	26		ug/L	25.00		103	70-130			
Surrogate: 4-Bromofluorobenzene	24.6		ug/L	25.00		98	70-130			
Surrogate: Dibromofluoromethane	25.6		ug/L	25.00		102	70-130			
Surrogate: Toluene-d8	24.8		ug/L	25.00		99	70-130			
LCS Dup (1805074-BSD1)				Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	27		ug/L	25.00		110	70-130	4	30	
Benzene	26		ug/L	25.00		104	70-130	5	30	
Chlorobenzene	26		ug/L	25.00		105	70-130	9	30	
Toluene	24		ug/L	25.00		96	70-130	5	30	
Trichloroethene	25		ug/L	25.00		98	70-130	4	30	
Surrogate: 4-Bromofluorobenzene	24.4		ug/L	25.00		98	70-130			
Surrogate: Dibromofluoromethane	26.1		ug/L	25.00		104	70-130			
Surrogate: Toluene-d8	25.1		ug/L	25.00		100	70-130			
Matrix Spike (1805074-MS1)		Source: 18D0582-02		Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	27		ug/L	25.00	0.070	109	70-130			
Benzene	26		ug/L	25.00	0.020	104	70-130			
Chlorobenzene	26		ug/L	25.00	0.0	105	70-130			
Toluene	27		ug/L	25.00	3.5	95	70-130			
Trichloroethene	24		ug/L	25.00	0.040	97	70-130			
Surrogate: 4-Bromofluorobenzene	24.4		ug/L	25.00		98	70-130			
Surrogate: Dibromofluoromethane	26.4		ug/L	25.00		106	70-130			
Surrogate: Toluene-d8	24.9		ug/L	25.00		100	70-130			
Matrix Spike Dup (1805074-MSD1)		Source: 18D0582-02		Prepared & Analyzed: 05/07/2018						
1,1-Dichloroethene	27		ug/L	25.00	0.070	108	70-130	0.8	30	
Benzene	25		ug/L	25.00	0.020	101	70-130	2	30	
Chlorobenzene	26		ug/L	25.00	0.0	105	70-130	0.3	30	
Toluene	27		ug/L	25.00	3.5	95	70-130	0.1	30	
Trichloroethene	24		ug/L	25.00	0.040	95	70-130	2	30	
Surrogate: 4-Bromofluorobenzene	24.7		ug/L	25.00		99	70-130			
Surrogate: Dibromofluoromethane	26.4		ug/L	25.00		106	70-130			
Surrogate: Toluene-d8	25.3		ug/L	25.00		101	70-130			

Client: Brown & Caldwell
Project: PTF
Work Order: 18D0619
Date Received: 04/25/2018

QC Summary

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qual
Batch 1804245 - E300.0 (2.1)										
Blank (1804245-BLK1)				Prepared & Analyzed: 04/25/2018						
Chloride	ND	1.0	mg/L							
Fluoride	ND	0.50	mg/L							
Nitrogen, Nitrate (As N)	ND	0.50	mg/L							
Nitrogen, Nitrite (As N)	ND	0.10	mg/L							
Sulfate	ND	5.0	mg/L							
LCS (1804245-BS1)				Prepared & Analyzed: 04/25/2018						
Chloride	12	1.0	mg/L	12.50		92	90-110			
Fluoride	2.0	0.50	mg/L	2.000		101	90-110			
Nitrogen, Nitrate (As N)	4.7	0.50	mg/L	5.000		95	90-110			
Nitrogen, Nitrite (As N)	2.3	0.10	mg/L	2.500		92	90-110			
Sulfate	12	5.0	mg/L	12.50		96	90-110			
LCS Dup (1804245-BS1)				Prepared & Analyzed: 04/25/2018						
Chloride	12	1.0	mg/L	12.50		94	90-110	2	10	
Fluoride	2.0	0.50	mg/L	2.000		101	90-110	0.4	10	
Nitrogen, Nitrate (As N)	4.9	0.50	mg/L	5.000		98	90-110	3	10	
Nitrogen, Nitrite (As N)	2.4	0.10	mg/L	2.500		95	90-110	3	10	
Sulfate	12	5.0	mg/L	12.50		98	90-110	3	10	
Matrix Spike (1804245-MS1)		Source: 18D0613-08		Prepared & Analyzed: 04/25/2018						
Fluoride	3.7	0.50	mg/L	2.000	1.7	100	80-120			
Nitrogen, Nitrate (As N)	4.7	0.50	mg/L	5.000	0.22	89	80-120			
Matrix Spike (1804245-MS2)		Source: 18D0625-01		Prepared & Analyzed: 04/26/2018						
Nitrogen, Nitrate (As N)	5.0	0.50	mg/L	5.000	0.46	92	80-120			
Nitrogen, Nitrite (As N)	2.2	0.10	mg/L	2.500	ND	88	80-120			
Matrix Spike (1804245-MS3)		Source: 18D0614-01RE1		Prepared & Analyzed: 04/26/2018						
Chloride	17		mg/L	12.50	6.4	88	80-120			
Sulfate	28		mg/L	12.50	18	85	80-120			
Matrix Spike Dup (1804245-MSD1)		Source: 18D0613-08		Prepared & Analyzed: 04/25/2018						
Fluoride	3.7	0.50	mg/L	2.000	1.7	100	80-120	0.4	10	
Nitrogen, Nitrate (As N)	4.7	0.50	mg/L	5.000	0.22	90	80-120	0.6	10	
Matrix Spike Dup (1804245-MSD2)		Source: 18D0625-01		Prepared & Analyzed: 04/26/2018						
Nitrogen, Nitrate (As N)	5.1	0.50	mg/L	5.000	0.46	92	80-120	0.2	10	
Nitrogen, Nitrite (As N)	2.2	0.10	mg/L	2.500	ND	88	80-120	0.4	10	
Matrix Spike Dup (1804245-MSD3)		Source: 18D0614-01RE1		Prepared & Analyzed: 04/26/2018						
Chloride	18		mg/L	12.50	6.4	89	80-120	0.6	10	
Sulfate	29		mg/L	12.50	18	86	80-120	0.6	10	



TURNER WORK ORDER # 18D0619 DATE 4/23/18 PAGE 1 OF 1

Page 13 of 32

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Phoenix

4625 East Cotton Ctr Blvd

Suite 189

Phoenix, AZ 85040

Tel: (602)437-3340

TestAmerica Job ID: 550-101943-1

Client Project/Site: 18D0619

For:

Turner Laboratories, Inc.

2445 North Coyote Drive

Suite 104

Tucson, Arizona 85745

Attn: Kevin Brim



Authorized for release by:

5/16/2018 12:23:25 PM

Ken Baker, Project Manager II

(602)659-7624

ken.baker@testamericainc.com

LINKS

Review your project
results through

TotalAccess

Have a Question?



Visit us at:

www.testamericainc.com

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

Table of Contents

Cover Page	1
Table of Contents	2
Definitions/Glossary	3
Case Narrative	4
Sample Summary	5
Detection Summary	6
Client Sample Results	7
Surrogate Summary	8
QC Sample Results	9
QC Association Summary	10
Lab Chronicle	11
Certification Summary	12
Method Summary	13
Chain of Custody	14
Receipt Checklists	15



Definitions/Glossary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Qualifiers

GC Semi VOA

Qualifier	Qualifier Description
Q9	Insufficient sample received to meet method QC requirements.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Case Narrative

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Job ID: 550-101943-1

Laboratory: TestAmerica Phoenix

Narrative

Job Narrative
550-101943-1

Comments

No additional comments.

Receipt

The sample was received on 4/27/2018 10:50 AM; the sample arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 3.8° C.

GC Semi VOA

Method(s) 8015D: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate/sample duplicate (MS/MSD) associated with preparation batch 550-145985 and analytical batch 550-146884. Affected samples have been added a Q9 qualifier. 18D0619-01 (550-101943-1)

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Organic Prep

Method(s) 3510C: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with 3510C.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Sample Summary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
550-101943-1	18D0619-01	Water	04/23/18 15:55	04/27/18 10:50

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

Detection Summary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Client Sample ID: 18D0619-01

Lab Sample ID: 550-101943-1

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
ORO (C22-C32)	0.21	Q9	0.20	mg/L	1		8015D	Total/NA

This Detection Summary does not include radiochemical test results.

Client Sample Results

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Client Sample ID: 18D0619-01

Date Collected: 04/23/18 15:55

Date Received: 04/27/18 10:50

Lab Sample ID: 550-101943-1

Matrix: Water

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
ORO (C22-C32)	0.21	Q9	0.20	mg/L		04/30/18 14:16	05/10/18 23:29	1
DRO (C10-C22)	ND	Q9	0.10	mg/L		04/30/18 14:16	05/10/18 23:29	1
Surrogate	%Recovery	Qualifier	Limits			Prepared	Analyzed	Dil Fac
o-Terphenyl (Surr)	79		10 - 150			04/30/18 14:16	05/10/18 23:29	1

Surrogate Summary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Method: 8015D - Diesel Range Organics (DRO) (GC)

Matrix: Water

Prep Type: Total/NA

Percent Surrogate Recovery (Acceptance Limits)		
Lab Sample ID	Client Sample ID	OTPH (10-150)
550-101943-1	18D0619-01	79
LCS 550-145985/2-A	Lab Control Sample	79
LCSD 550-145985/3-A	Lab Control Sample Dup	79
MB 550-145985/1-A	Method Blank	65

Surrogate Legend

OTPH = o-Terphenyl (Surr)

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

QC Sample Results

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Method: 8015D - Diesel Range Organics (DRO) (GC)

Lab Sample ID: MB 550-145985/1-A

Matrix: Water

Analysis Batch: 146884

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 145985

Analyte	MB Result	MB Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
ORO (C22-C32)	ND		0.20	mg/L		04/30/18 14:15	05/11/18 11:16	1
DRO (C10-C22)	ND		0.10	mg/L		04/30/18 14:15	05/11/18 11:16	1
Surrogate	MB %Recovery	MB Qualifier	Limits			Prepared	Analyzed	Dil Fac
o-Terphenyl (Surr)	65		10 - 150			04/30/18 14:15	05/11/18 11:16	1

Lab Sample ID: LCS 550-145985/2-A

Matrix: Water

Analysis Batch: 146884

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Prep Batch: 145985

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
ORO (C22-C32)	1.60	1.59		mg/L		99	69 - 107
DRO (C10-C22)	0.400	0.450		mg/L		113	42 - 133
Surrogate	LCS %Recovery	LCS Qualifier	Limits				
o-Terphenyl (Surr)	79		10 - 150				

Lab Sample ID: LCSD 550-145985/3-A

Matrix: Water

Analysis Batch: 146884

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Prep Batch: 145985

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
ORO (C22-C32)	1.60	1.59		mg/L		100	69 - 107	0	20
DRO (C10-C22)	0.400	0.447		mg/L		112	42 - 133	1	22
Surrogate	LCSD %Recovery	LCSD Qualifier	Limits						
o-Terphenyl (Surr)	79		10 - 150						

TestAmerica Phoenix

QC Association Summary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

GC Semi VOA

Prep Batch: 145985

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
550-101943-1	18D0619-01	Total/NA	Water	3510C	
MB 550-145985/1-A	Method Blank	Total/NA	Water	3510C	
LCS 550-145985/2-A	Lab Control Sample	Total/NA	Water	3510C	
LCSD 550-145985/3-A	Lab Control Sample Dup	Total/NA	Water	3510C	

Analysis Batch: 146884

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
550-101943-1	18D0619-01	Total/NA	Water	8015D	145985
MB 550-145985/1-A	Method Blank	Total/NA	Water	8015D	145985
LCS 550-145985/2-A	Lab Control Sample	Total/NA	Water	8015D	145985
LCSD 550-145985/3-A	Lab Control Sample Dup	Total/NA	Water	8015D	145985

Lab Chronicle

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Client Sample ID: 18D0619-01

Date Collected: 04/23/18 15:55

Date Received: 04/27/18 10:50

Lab Sample ID: 550-101943-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3510C			145985	04/30/18 14:16	REM	TAL PHX
Total/NA	Analysis	8015D		1	146884	05/10/18 23:29	TC1	TAL PHX

Laboratory References:

TAL PHX = TestAmerica Phoenix, 4625 East Cotton Ctr Blvd, Suite 189, Phoenix, AZ 85040, TEL (602)437-3340

Accreditation/Certification Summary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Laboratory: TestAmerica Phoenix

Unless otherwise noted, all analytes for this laboratory were covered under each accreditation/certification below.

Authority	Program	EPA Region	Identification Number	Expiration Date
Arizona	State Program	9	AZ0728	06-09-18
Analysis Method	Prep Method	Matrix	Analyte	

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15

Method Summary

Client: Turner Laboratories, Inc.
Project/Site: 18D0619

TestAmerica Job ID: 550-101943-1

Method	Method Description	Protocol	Laboratory
8015D	Diesel Range Organics (DRO) (GC)	SW846	TAL PHX
3510C	Liquid-Liquid Extraction (Separatory Funnel)	SW846	TAL PHX

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL PHX = TestAmerica Phoenix, 4625 East Cotton Ctr Blvd, Suite 189, Phoenix, AZ 85040, TEL (602)437-3340

SUBCONTRACT ORDER

Turner Laboratories, Inc.

18D0619

101943

SENDING LABORATORY:

Turner Laboratories, Inc.
2445 N. Coyote Drive, Ste #104
Tucson, AZ 85745
Phone: 520.882.5880
Fax: 520.882.9788
Project Manager: Kevin Brim

RECEIVING LABORATORY:

TestAmerica Phoenix
4625 East Cotton Center Boulevard Suite 189
Phoenix, AZ 85540
Phone : (602) 437-3340
Fax:
Please CC Kevin Brim Kbrim@turnerlabs.com

Analysis

Expires

Laboratory ID

Comments

Sample ID: 18D0619-01 Drinking Water Sampled: 04/23/2018 15:55

8015D Sub

04/30/2018 15:55

8015D DRO and ORO Paramaters Only

Containers Supplied:

8015D Sub

o-Terphenyl
C10-C32 (Total)
C22-C32 (Oil Range Organics)
C10-C22 (Diesel Range Organics)
C6-C10 (Gasoline Range Organics)

550-101943 Chain of Custody



TA-PHX

3.8 L
LPS
GVR

Released By

Date

Received By

Date

Released By

Date

Received By

Date

Login Sample Receipt Checklist

Client: Turner Laboratories, Inc.

Job Number: 550-101943-1


Login Number: 101943

List Source: TestAmerica Phoenix

List Number: 1

Creator: Gravlin, Andrea

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	False	Check done at department level as required.



Radiation Safety Engineering, Inc.

3245 N. WASHINGTON ST. • CHANDLER, ARIZONA 85225-1121

(480) 897-9459

Website: www.radsafe.com

FAX (480) 892-5446


Radiochemical Activity in Water (pCi/L)

Turner Laboratories
2445 N. Coyote Drive, Ste. 104
Tucson, AZ 85745

Sampling Date: April 23, 2018
Sample Received: May 01, 2018
Analysis Completed: May 22, 2018

Sample ID	Gross Alpha Activity Method 600/00-02 (pCi/L)	Uranium Activity Method ASTM D6239 (pCi/L)	Adjusted Gross Alpha (pCi/L)	Radium 226 Activity Method GammaRay HPGE (pCi/L)	Radium 228 Activity Method GammaRay HPGE (pCi/L)	Total Radium (pCi/L)
18D0619-01	17.7 ± 0.9	12.9 ± 1.2	4.8 ± 1.5	3.1 ± 0.3	3.1 ± 0.4	6.2 ± 0.5

Date of Analysis	5/2/2018	5/21/2018	5/21/2018	5/4/2018	5/4/2018	5/4/2018
------------------	----------	-----------	-----------	----------	----------	----------


 Robert L. Metzger, Ph.D., C.H.P. 5/22/2018
 Date
 Laboratory License Number AZ0462



Radiation Safety Engineering, Inc.

3245 N. WASHINGTON ST. • CHANDLER, ARIZONA 85225-1121

Website: www.radsafe.com

(480) 897-9459

FAX (480) 892-5446

Isotopic Uranium Analysis

Turner Laboratories
2445 N. Coyote Drive, Ste. 104
Tucson, AZ 85745

Sampling Date: April 23, 2018

Sample Received: May 01, 2018

Uranium Analysis Date: May 21, 2018

Sample No.	^{238}U	^{235}U	^{234}U	Total	
18D0619-01	6.0 ± 0.6	0.280 ± 0.004	6.6 ± 0.6	12.9 ± 1.2	Activity (pCi/L)
	17.9 ± 1.7	0.131 ± 0.002	0.00106 ± 0.00010	18.0 ± 1.7	Content ($\mu\text{g/L}$)
	Comments:				

Robert L. Metzger
Robert L. Metzger, Ph.D., C.H.P.

5/22/2018

Date

Laboratory License Number AZ0462

Arizona Department of Environmental Quality
Drinking Water Radionuclides-Adjusted Gross Alpha, Radium 226 & 228, Uranium Analysis Report
 Samples To Be Taken At Entry Point Into Distribution System (EPDS) Only

PWS ID#: AZ04

PWS Name: _____

April 23, 2018 15:55 (24 hour clock)

Sample Date

Sample Time

Owner/Contact Person

Owner/Contact Fax Number

Owner/Contact Phone Number

Sample Collection Point

☐ EPDS # _____**Compliance Sample Type:**☐

Reduced Monitoring

Date Q1 collected: _____

☐

Quarterly

Date Q2 collected: _____

☐

Composite of four quarterly samples

Date Q3 collected: _____

Date Q4 collected: _____

*****RADIOCHEMICAL ANALYSIS*****

>>>To be filled out by laboratory personnel<<<

*****Combined Uranium must be reported in micrograms per liter*****

Analysis Method	MCL	Reporting Limit	Contaminant Name	Cont. Code	Analyses Run Date	Result	Exceed MCL
	15 pCi/L		Adjusted Gross Alpha	4000	5/21/2018	4.8 ± 1.5	
600/00-02		3 pCi/L	Gross Alpha	4002	5/2/2018	17.7 ± 0.9	
7500 - Rn			Radon	4004			
ASTM D6239	30 µg/L	1 µg/L	Combined Uranium	4006	5/21/2018	18.0 ± 1.7 µg/L	
			Uranium 234	4007	5/21/2018	0.00106 ± 0.00010	
			Uranium 235	4008	5/21/2018	0.131 ± 0.002	
			Uranium 238	4009	5/21/2018	17.9 ± 1.7	
	5 pCi/L	1 pCi/L	Combined Radium (226,228)	4010	5/4/2018	6.2 ± 0.5	X
GammaRay HPGE		1 pCi/L	Radium 226	4020	5/4/2018	3.1 ± 0.3	
GammaRay HPGE		1 pCi/L	Radium 228	4030	5/4/2018	3.1 ± 0.4	

*****LABORATORY INFORMATION*****

>>>To be filled out by laboratory personnel<<<


Specimen Number: RSE60312

Lab ID Number: AZ0462

Lab Name: Radiation Safety Engineering, Inc.

Printed Name and Phone Number of Laboratory Contact: Robert L. Metzger, Ph.D., C.H.P. (480) 897-9459

Comments: 18D0619-01

Authorized Signature: 

Date Public Water System Notified: _____

DWAR 6: 11/2007

SUBCONTRACT ORDER

Turner Laboratories, Inc.

18D0619

SENDING LABORATORY:

Turner Laboratories, Inc.
2445 N. Coyote Drive, Ste #104
Tucson, AZ 85745
Phone: 520.882.5880
Fax: 520.882.9788
Project Manager: Kevin Brim

RECEIVING LABORATORY:

Radiation Safety Engineering, Inc.
3245 N. Washington St.
Chandler, AZ 85225-1121
Phone : (480) 897-9459
Fax: (480) 892-5446
Please CC Kevin Brim Kbrim@turnerlabs.com

Analysis	Expires	Laboratory ID	Comments
<hr/>			
Sample ID: 18D0619-01 Drinking Water Sampled: 04/23/2018 15:55			
Radiochemistry, Gross Alpha	10/20/2018 15:55		Analyze Uranium and Adjusted Alpha if G. Alpha is > 12
Radiochemistry, Radium 226/228	05/23/2018 15:55		
Containers Supplied:			

H 60312

Released By

Date

4/30/18

16:00

ups

Received By

4/30/18

Date

16:00

Released By

Date

Received By

Date

APPENDIX D

Well Completion Documentation

PIPE TALLY

Project Name.: FLORENCE COPPER	Project No.: 129671-200
Well No.: M55-WBF	Date: 4/11/2017
Location:	Pipe Tally for: WELL CASING / SCREEN
Total Depth: 260 FT	Geologist: L. CANDREVA

Type of Connections: ☐ Welded ☒ T+C ☐ Flush Thread ☐ Other

Pipe	✓	Length (ft)	Length Σ (ft)	Pipe Type	Pipe	✓	Length (ft)	Length Σ (ft)	Pipe Type
1	✓	0.54	0.54	ENDCAP	X				
2	✓	20.04	20.58	SCREEN					
3	✓	1.28	21.86	CROSSOVER					
4	✓	20.01	41.87	CASING					
5	✓	20.01	61.88						
6	✓	20.00	81.88						
7	✓	20.00	101.88						
8	✓	20.00	121.88						
9	✓	20.00	141.88						
10		19.99	161.87						
11		20.00	181.87						
12		19.99	201.86						
13		20.01	221.87						
14		20.00	241.87						
15		19.99	261.86						
X					X				
					SUMMARY OF TALLY				
					Total Length tallied: 261.86				
					Casing Stick-Up: 1.3				
					Length of Casing Cut-Off: 260.56				
					Bottom of Well: 259.2898 - 260.02				
					Screened Interval: 20.04				
					Total Screen in Hole: 20.04				

Notes:

ENDCAP - SCHEDULE 80 PVC FLUSH-THREADED W/O-RING, 5-INCH NOM DIAMETER

SCREEN - SCH 80 PVC, FLUSH-THREADED W/ O-RING, 5-INCH NOMINAL DIAMETER, 0.020-INCH WIDE SLOTS

CROSSOVER - MILD STEEL-FLUSH-THREADED CONN FROM 5-INCH NOM. PVC TO 5 5/8-INCH O.D. MILD STEEL CASING

CASING - 5 5/8-INCH O.D., 0.258-INCH WALL THICKNESS LONGITUDINALLY WELDED MILD STEEL, FLUSH-THREADED

K:\Templates\Field Forms\Well Inst & Testing Forms.xls\Well Inst & Testing Forms.xls

⊕ INDICATE CONNECTION W/ CENTRALIZER

ESTIMATED ANNULAR MATERIAL RECORD

Project Name: LORENCE COPPER Project #: 29087-002 Date: 4/11/2017
Well No.: W55-UBF Geologist: L. CANDREVA / C. PRICE

ANNULAR VOLUME CALCULATIONS

Total Depth of Borehole [T]: 272 feet
Borehole Diameter [D]: 10.63 inches
Screen Length [L_s]: 20 feet
Screen Diameter [d_s]: 5.63 inches
Casing Length [L_c]: 240 feet
Casing Diameter [d_c]: 5.63 inches

Total Cased Depth: 260.5 feet
Rat Hole Volume [R=(D² 0.005454*L_r): 7.1 Ft³
Rat Hole Length [L_r]: 11.5 feet
Camera Tube Length [L_{ct}]: - feet
Camera Tube Diameter [d_{ct}]: - inches

Screen Annular Volume (A_s): (D²-d_s²) 0.005454 = 0.44 Ft³/Lin. Ft
Casing Annular Volume (A_c): (D²-d_c²) 0.005454 = 0.44 Ft³/Lin. Ft
Casing/Cam.Tube Annular Volume (A_{c+ct}): (D²-d_c²-d_{ct}²) 0.005454 = - Ft³/Lin. Ft
Tot vol = 140.1 ft³

EQUATIONS

2,700 lbs. Silica Sand = 1 cubic yard = 27 cubic feet


Bentonite Sack = 0.69 ft³

¹ Volume of bag (Ft³) = bag weight/100

Silica Sand Super Sack = 3000 lbs.

² Calculated depth = Previous Calculated depth - (v/A)

No.	✓	Weight of Bag (lbs.)	Volume of Bag ¹ (v) (ft ³)	Total Vol. of Bags (ft ³)	Calculated Depth ² (ft bls)	Tagged Depth (ft bls)	Comments
-	✓	1340	13.42	13.42	247	245	20.5 gal BKTS 8-12 SAND
	✓	536	5.36	18.78	235	239	8.5 gal BKTS 8-12 SAND
	✓	335	3.35	22.13	227	230	5.5 gal BKTS 8-12 SAND
	✓	50	0.5	22.63	228	NA	1-56 lbs bag #60 SAND
	✓	300	3	25.63	221	216	6.5 gal BKTS 1/4 PER LBS TRSG
	✓	-	137	163	-128	0	Cemex type V, 14.8 lbs/gal 5.5 yards, used just over 5.



RAT HOLE = 7.1 ft³ = 53 gal = 10.6 BKTS

SCR INT = 13.42 ft³ = 100.4 gal = 20.1 BKTS

7.48 gals = 1 ft³ 30.7 BKTS



54017394

Plant:	Begin Loading:	To Job:	Arrive Job:	Start Unload:	Finish Unload:	Leave Job:	Return Plant:
DIC 4112	1202	1210	0100				

Customer Code: 0181157	Customer Name: FLORENCE COPPER INC	Customer Job Number: FLORENCE WELL	Order Code / Date: 6382 04/12/17
Project Code: 41097304	Project Name: FLORENCE WELL	Project P.O. Number: NO	Order P.O. Number: NO
Ticket Date: 04/12/17	Delivery Address: 1575 W HUNT HIGHWAY	CEMEX ONE	Map Page: Map/Row/Column: PIN PINMY201
Delivery Instructions: HUNT HWY & E/ FELIX R			Dispatcher: dbeesley
			Ticket Number: 44089958

Due On Job:	Slump:	Truck Number:	Driver Number:	Driver Name:	End Use:
0100	11.00	10032179	411205	SLATER, GREGORY	FLT BLDNG: OTHER

LOAD QUANTITY	CUMULATIVE QUANTITY	ORDERED QUANTITY	MATERIAL CODE	PRODUCTION DESCRIPTION	UOM	UNIT PRICE	AMOUNT
5.50	5.50	5.50	1333049	TYPE II/V SLURRY 21 SK. CMT/W YD3			
				LEGACY MATERIAL NO:			
1.00	1.00	1.00	1349968	SATURDAY OPENING	EA		
1.00			1247818	FUEL SURCHARGE ADJ			
1.00			1202749	ENVIRONMENTAL FEE			
1.00			1572392	FREIGHT_NON_TAXABLE_ARIZONA			

APR 12 AM 12:14

<input type="checkbox"/> Cash <input type="checkbox"/> Check <input type="checkbox"/> Charge	Check # / Auth Code:	Signature of Driver Receiving Cash:	Cash Received:	Total COD Order Amount to Collect Without Standby Charges:
Comments:			WATER ADDED: _____ GAL YARDS IN DRUM: _____ WHEN ADDED.	
			SIGNATURE	
			CURB LINE CROSSED AT OWNER'S/AGENT'S REQUEST:	
			SIGNATURE	
			<input type="checkbox"/> LOAD WAS TESTED BY: _____	

Notice: Our drivers will make every effort to place materials where the customer designates, but the Company assumes no responsibility for damages inside curb or property line. Customer agrees to the terms of sale and delivery and accepts concrete as is. Due to important factors which are out of our control after delivery, this Company will not accept any responsibility for the finished results. No credit for returned concrete. Buyers exceptions and claims shall be deemed waived unless made to us in writing within one business day after the receipt of materials.

SPECIAL TERMS: Any water added is at customers own risk. If water is added on job, concrete strength is no longer guaranteed. WARNING: Product may cause skin and/or eye irritation. CAUTION: Material may be hazardous to your safety and health. Please refer to the backside of this ticket for important safety handling information, and to the material safety data sheets for additional information.

AUTHORIZED SIGNATURE:

ⓧ

68UNIVERSAL

PRE / TRK:

CUSTOMER

LOAD NUM: 1

APPENDIX E

Geophysical Logs



Southwest Exploration Services, LLC


borehole geophysics & video services


COMPANY		FLORENCE COPPER	
WELL ID		M55-UBF	
FIELD		FLORENCE COPPER	
COUNTY		PINAL	
STATE		ARIZONA	
TYPE OF LOGS: E-LOGS MORE: NAT. GAMMA		OTHER SERVICES SONIC DEVIATION CALIPER TEMP/FLUID RES.	
LOCATION			
SEC		TWP	
RGE			
PERMANENT DATUM		ELEVATION	
LOG MEAS. FROM		GROUND LEVEL	
ABOVE PERM. DATUM			
DRILLING MEAS. FROM		GROUND LEVEL	
DATE		4-11-17	
TYPE LOG		E-LOG-GAMMA	
DEPTH-DRILLER		272 FT.	
DEPTH-LOGGER		272 FT.	
BTM LOGGED INTERVAL		272 FT.	
TOP LOGGED INTERVAL		SURFACE	
DRILLER / RIG#		NATIONAL	
RECORDED BY / Logging Eng.		E. TURNER	
WITNESSED BY		NATIONAL	
LOG TIME:ON SITE/OFF SITE		12:00 PM	
RUN		BOREHOLE RECORD	
NO.		BIT	
FROM		TO	
SURFACE		40 FT.	
TOTAL DEPTH			
COMMENTS:			

Tool Summary:					
Date	4-11-17	Date	4-11-17	Date	4-11-17
Run No.	1	Run No.	2	Run No.	3
Tool Model	MSI COMBO TOOL	Tool Model	MSI POLYPROBE	Tool Model	MSI 60MM SONIC
Tool SN	4183	Tool SN	3604	Tool SN	6003
From	SURFACE	From	SURFACE	From	SURFACE
To	272 FT.	To	272 FT.	To	272 FT.
Recorded By	E. TURNER	Recorded By	E. TURNER	Recorded By	E. TURNER
Truck No	900	Truck No	900	Truck No	900
Operation Check	4-9-17	Operation Check	4-9-17	Operation Check	4-9-17
Calibration Check	3-25-17	Calibration Check	3-25-17	Calibration Check	N/A
Time Logged	12:20 PM	Time Logged	1:00 PM	Time Logged	1:30 PM
Date	4-11-17	Date		Date	
Run No.	4	Run No.	5	Run No.	6
Tool Model	MSI 2DVA	Tool Model		Tool Model	
Tool SN	3082	Tool SN		Tool SN	
From	SURFACE	From		From	
To	272 FT	To		To	
Recorded By	E. TURNER	Recorded By		Recorded By	
Truck No	900	Truck No		Truck No	
Operation Check	4-9-17	Operation Check		Operation Check	
Calibration Check	N/A	Calibration Check		Calibration Check	
Time Logged	2:15 PM	Time Logged		Time Logged	
Additional Comments:					
Caliper Arms Used: 9 IN.		Calibration Points: 3.5 IN. & 16 IN.			

Disclaimer:

All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.






MSI PolyElectric Tool

Probe Top = Depth Ref.

Tool SN: 4067 & 3604

Bridle connects to wireline cablehead: Wireline armor is the B Electrode.



64" Normal Resistivity Electrode/Spontaneous Potential Electrode (M Electrode)

Probe Length = 2.21 m or 7.25 ft


Probe Length = 2.21 m or 7.24 ft
Bridle Length = 7.88 m or 25.86 ft

Probe Weight = 10.0 kg or 22.0 lbs

Can only be collected in fluid

Requires a "mudfish" to be used

Bridle can be optionally used if the wireline is isolated with electrical tape



**Southwest Exploration
Services, LLC**

borehole geophysics & video services

Company FLORENCE COPPER

Well M55-UBF
Field FLORENCE COPPER
County PINAL
State ARIZONA

Final

E-Log Summary




Southwest Exploration Services, LLC


borehole geophysics & video services

COMPANY FLORENCE COPPER									
WELL ID M55-UBF									
FIELD FLORENCE COPPER									
COUNTY PINAL STATE ARIZONA									
TYPE OF LOGS: GAMMA-CALIPER						OTHER SERVICES E-LOGS SONIC DEVIATION			
MORE: TEMP - FLUID RES.									
LOCATION									
PERMANENT DATUM		SEC		TWP		RGE		ELEVATION	
LOG MEAS. FROM		GROUND LEVEL		ABOVE PERM. DATUM		D.F.		K.B.	
DRILLING MEAS. FROM		GROUND LEVEL		G.L.		MUD			
DATE	4-11-17	TYPE FLUID IN HOLE		MUD WEIGHT		N/A			
RUN No	1	GAMMA-CALIPER-TFR		VISCOSITY		N/A			
TYPE LOG		272 FT.		LEVEL		FULL			
DEPTH-DRILLER		272 FT.		MAX. REC. TEMP.		31.4 DEG. C			
DEPTH-LOGGER		272 FT.		IMAGE ORIENTED TO:		N/A			
BTM LOGGED INTERVAL		272 FT.		SAMPLE INTERVAL		0.2 FT			
TOP LOGGED INTERVAL		SURFACE		LOGGING TRUCK		TRUCK #900			
DRILLER / RIG#		NATIONAL		TOOL STRING/SN		MSI COMBO TOOL SN 4183			
RECORDED BY / Logging Eng.		E. TURNER		LOG TIME:ON SITE/OFF SITE		12:00 PM			
WITNESSED BY		NATIONAL							
BOREHOLE RECORD									
RUN NO.	BIT	FROM	TO	SIZE	WGT.	FROM	TO		
1	?	SURFACE	40 FT.	14 IN.	STEEL	SURFACE	40 FT.		
2	10 5/8 IN.	40 FT.	TOTAL DEPTH						
3									
COMMENTS:									

Disclaimer:


All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.





MSI Gamma-Caliper-Temperature-Fluid Resistivity

Probe Top = Depth Ref.



Single Conductor MSI Probe Top

Probe Length = 2.59 m or 8.5 ft

Probe Weight = 6.80 kg or 15.0 lbs

Natural Gamma and Caliper can only be collected logging up hole.


Fluid Temperature/Resistivity can only be collected logging down hole.

Temperature Rating: 70 Deg C (158 Deg F)

Pressure Rating: 200 bar (2900 psi)

Natural Gamma Ray = 0.76 m (29.75 in)

NOTE: Lengths on a particular tool may vary from those listed on this document due to probe sizes and styles utilized



————— **3-Arm Caliper = 1.44 m (56.75 in)**

Distance from tool top: 2.20 m (86.5 in)

Available Arm Sizes: 3", 9", and 15"

————— **TFR (Temperature/Fluid Resistivity) = 0.39 m (15.5 in)**

1.375" or 34.9 mm Diameter



**Southwest Exploration
Services, LLC**

borehole geophysics & video services

Company FLORENCE COPPER

Well M55-UBF
Field FLORENCE COPPER
County PINAL
State ARIZONA

Final

GCT Summary




Southwest Exploration Services, LLC

borehole geophysics & video services

COMPANY FLORENCE COPPER									
WELL ID M55-UBF									
FIELD FLORENCE COPPER									
COUNTY PINAL STATE ARIZONA									
TYPE OF LOGS: 60mm SONIC MORE: CALIPER-GAMMA									
LOCATION									
OTHER SERVICES E-LOGS COMBO TOOL DEVIATION									
PERMANENT DATUM		SEC		TWP		RGE		ELEVATION	
LOG MEAS. FROM		GROUND LEVEL		ABOVE PERM. DATUM		D.F.		K.B.	
DRILLING MEAS. FROM		GROUND LEVEL		G.L.		MUD			
DATE		4-11-17		TYPE FLUID IN HOLE		MUD WEIGHT		N/A	
RUN No		1 / 3		SONIC-GAMMA-CAL		VISCOSITY		N/A	
TYPE LOG		272 FT.		LEVEL		MAX. REC. TEMP.		FULL	
DEPTH-DRILLER		272 FT.		IMAGE ORIENTED TO:		N/A		0.25 FT	
DEPTH-LOGGER		272 FT.		LOGGING TRUCK		TRUCK #900			
BTM LOGGED INTERVAL		272 FT.		TOOL STRING/SN		MSI 60MM SONIC SN 6003			
TOP LOGGED INTERVAL		SURFACE		LOG TIME:ON SITE/OFF SITE		12:00 PM			
DRILLER / RIG#		NATIONAL							
RECORDED BY / Logging Eng.		E. TURNER							
WITNESSED BY		NATIONAL							
RUN BOREHOLE RECORD									
CASING RECORD									
NO.		BIT		FROM		TO		SIZE	
1		?		SURFACE		40 FT.		14 IN.	
2		10 5/8 IN.		40 FT.		TOTAL DEPTH			
3									
COMMENTS:									

Disclaimer:

All interpretations of log data are opinions based on inferences from electrical or other measurements. We do not guarantee the accuracy or correctness of any interpretations or recommendations and shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our employees or agents. These interpretations are also subject to our general terms and conditions set out in our current Service Invoice.




Typically centralized with external centralizers

Can only be collected in fluid

Temperature Rating: 80 Deg C (176 Deg F)

Pressure Rating: 200 bar (2900 psi)



2.36 in or 60 mm Diameter

MSI Gamma-Caliper-Temperature-Fluid Resistivity

Probe Top = Depth Ref.



Probe Length = 2.59 m or 8.5 ft

Probe Weight = 6.80 kg or 15.0 lbs

Natural Gamma and Caliper can only be collected logging up hole.

Fluid Temperature/Resistivity can only be collected logging down hole.

Temperature Rating: 70 Deg C (158 Deg F)
Pressure Rating: 200 bar (2900 psi)

———— Natural Gamma Ray = 0.76 m (29.75 in)

NOTE: Lengths on a particular tool may vary from those listed on this document due to probe sizes and styles utilized

———— 3-Arm Caliper = 1.44 m (56.75 in)

Distance from tool top: 2.20 m (86.5 in)

Available Arm Sizes: 3", 9", and 15"

———— TFR (Temperature/Fluid Resistivity) = 0.39 m (15.5 in)

1.375" or 34.9 mm Diameter



**Southwest Exploration
Services, LLC**

borehole geophysics & video services

Company	FLORENCE COPPER
Well	M55-UBF
Field	FLORENCE COPPER
County	PINAL
State	ARIZONA

Final

Sonic Summary

Drift Report

Wellbore DRIFT Interpretation

PREPARED ESPECIALLY FOR

FLORENCE COPPER

M55-UBF

Tuesday - April 11, 2017



This Wellbore Interpretation Package represents our best efforts to provide a correct interpretation. Nevertheless, since all interpretations are opinions based on inferences from electrical or other types of measurements, we cannot and do not guarantee the accuracy or correctness of any interpretation, and we shall not be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by Customer resulting from any interpretation made by this document. We do not warrant or guarantee the accuracy of the data, specifically including (but without limitations) the accuracy of data transmitted by electronic process, and we will not be responsible for accidental or intentional interception of such data by third parties. Our employees are not empowered to change or otherwise modify the attached interpretation. Furthermore, along with Eagle Pro Software we do not warrant or guarantee the accuracy of the programming techniques employed to produce this document. By accepting this Interpretation Package, the Customer agrees to the foregoing, and to our General Terms and Conditions.

Southwest Exploration Services, LLC
(480) 926-4558

WELLBORE DRIFT INTERPRETATION

Southwest Exploration Services, LLC

(480) 926-4558

Company:	FLORENCE COPPER			Well Owner:								
County:	PINAL	State:	Arizona		Country:	USA						
Well Number:	M55-UBF	Survey Date:	Tuesday - April 11, 2017		Magnetic Declination:	Declination Correction Not Used						
Field:	FLORENCE COPPER		Drift Calculation Methodology:			Balanced Tangential Method						
Location:												
Remarks:												
Witness:	NATIONAL	Vehicle No.:	900	Invoice No.:		Operator:	E, TURNER	Well Depth:	272 Feet	Casing size:	10.625 Inches	
Tool:	Compass - 6002		Lat.:		Long.:		Sec.:		Twp.:		Rge.:	

MEASURED DATA			DATA COMPUTATIONS						
DEPTHS, feet	INCLINATIONS, degrees	AZIMUTHS, degrees	TVD, feet	T. LATITUDE, feet	T. LONGITUDE, feet	DOGLEG SEV., degrees per 20 Feet	DOGLEG SEV., degrees per 100 feet	DRIFT DIST., feet	DRIFT BGR., degrees
20	0.33	051.55	20.00						
40	0.24	031.51	39.99	0.072	0.067	0.42	0.40	0.10' (1.20")	043.10
60	0.34	094.58	59.98	0.103	0.148	0.96	1.20	0.18' (2.16")	055.20
80	0.18	104.65	79.97	0.090	0.238	0.84	0.20	0.25' (3.00")	069.20
100	0.12	129.93	99.97	0.069	0.284	0.42	0.50	0.29' (3.48")	076.40
120	0.35	167.97	119.96	-0.004	0.313	0.14	0.75	0.31' (3.72")	090.80
140	0.52	227.47	139.95	-0.125	0.259	0.43	1.14	0.29' (3.48")	115.80
160	0.39	287.46	159.94	-0.166	0.127	0.83	1.15	0.21' (2.52")	142.50
180	0.14	282.70	179.93	-0.140	0.038	0.95	0.10	0.15' (1.80")	164.70
200	0.06	231.21	199.92	-0.141	0.006	0.38	1.00	0.14' (1.68")	177.60
220	0.09	223.09	219.91	-0.159	-0.013	1.00	0.16	0.16' (1.92")	184.60
240	0.23	278.84	239.90	-0.164	-0.063	1.00	1.08	0.18' (2.16")	201.10
260	0.23	242.82	259.89	-0.176	-0.138	0.35	0.71	0.22' (2.64")	218.10

APPENDIX F

SAPT Documentation

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
STANDARD ANNULAR PRESSURE TEST

Operator FLORENCE COPPER, INC

State Permit No. P-101704

Address 1575 W. HUNT HWY

USEPA Permit No. R9UIC-AZ3-FY11-1

FLORENCE, AZ 85132

Date of Test 6/23/2017

Well Name M55-UBF

Well Type CLASS III - SUPPL. MONITORING

LOCATION INFORMATION

SE Quarter of the NW Quarter of the SW Quarter
of Section 28 ; Range 9E ; Township 4S ; County PINAL ;

Company Representative IAN REAM ; Field Inspector LAUREN CANDREVA ;

Type of Pressure Gauge 2 inch face; 300 psi full scale; 1 psi increments;

New Gauge? Yes ☒ No ☐ If no, date of calibration Calibration certification submitted? Yes ☐ No ☒

TEST RESULTS

Readings must be taken at least every 10 minutes for a minimum of 30 minutes for Class II, III and V wells and 60 minutes for Class I wells.

For Class II wells, annulus pressure should be at least 300 psig. For Class I wells, annulus pressure should be the greater of 300 psig or 100 psi above maximum permitted injection pressure.

Original chart recordings must be submitted with this form.

5-year or annual test on time? Yes ☐ No ☒

2-year test for TA'd wells on time? Yes ☐ No ☒

After rework? Yes ☐ No ☒

Newly permitted well? Yes ☒ No ☐

Time	Pressure (in psig)	
	Annulus	Tubing
14:00	210	same
14:10	140	same
14:15	117	same

Casing size 5" - NOMINAL

Tubing size 2"

Packer type INFLATABLE PACKER

Packer set @ 199.4 feet

Top of Permitted Injection Zone None

Is packer 100 ft or less above top of

Injection Zone ? Yes ☐ No ☒

If not, please submit a justification.

Fluid return (gal.)

Comments: Monitoring well completed approx. 150 feet above the top of the permitted injection zone

Test Pressures: Max. Allowable Pressure Change: Initial test pressure x 0.05 10.5 psi

Test Period Pressure change 93 psi

Test Passed ☐

Test Failed ☒

If failed test, well must be shut in, no injection can occur, and USEPA must be contacted within 24 hours. Corrective action needs to occur, the well retested, and written authorization received before injection can recommence.

I certify under penalty of law that this document and all attachments are, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. (See 40 CFR 144.32(d))

IAN REAM
Printed Name of Company Representative


Signature of Company Representative

9-14-2018
Date

APPENDIX G

Cement Bond Log Summary

WELL M55-UBF

Geophysical Log Summary





Southwest Exploration Services, LLC
borehole geophysics & video services



COMPANY: FLORENCE COPPER COMPANY
FIELD: FLORENCE COPPER SITE
WELL ID: M55-UBF
COUNTY: PINAL STATE: ARIZONA

Logging Engineer: VARIOUS
Date Logged: VARIOUS
Processed By: K.M / B.C.
Date Processed: 09-09-18





Version 09-10-18 EJB

<div><div>-2g/cc2</div><div>Cased 5-12-17</div><div>Compensation</div></div>		<div><div>0%100</div><div>Open 4-11-17</div><div>Bond Index (60mm)</div></div>		<div><div>0%100</div><div>Cased 5-12-17</div><div>Bond Index</div></div>		<div><div>40us/ft220</div><div>PVC</div><div>40us/ft220</div><div>FRP</div><div>40us/ft220</div><div>Steel</div><div>40uSec/ft220</div><div>Cased 5-12-17</div><div>P-Wave Slow</div></div>		<div><div>200CPS0</div><div>Cased 5-12-17</div><div>4 Pi Density (Wet)</div><div>500CPS300</div><div>Cased 5-12-17</div><div>4 Pi Density (Dry)</div><div>1g/cc3</div><div>Cased 5-12-17</div><div>Far Density</div></div>
<div><div>1g/cc3</div><div>Cased 5-12-17</div><div>Comp Density</div></div>		<div><div>100uSec1000</div><div>Open 4-11-17</div><div>RX1 - TT (60mm)</div></div>		<div><div>100uSec1020</div><div>Cased 5-12-17</div><div>RX1 - TT</div></div>		<div><div>100uSec1020</div><div>Cased 5-12-17</div><div>RX4 - TT</div></div>		

	<div>010inches</div> <div>Cased 5-12-17</div> <div>1-Arm Caliper</div>	<div>1001000uSec</div> <div>Open 4-11-17</div> <div>RX1 - VDL (60mm)</div>	<div>1001020uSec</div> <div>Cased 5-12-17</div> <div>RX1 - VDL</div>	<div>1001020uSec</div> <div>Cased 5-12-17</div> <div>RX4 - VDL</div>	<div>40220uS/ft</div> <div>Cased 5-12-17</div> <div>Velocity Analysis</div>	<div>15g/cc</div> <div>Cased 5-12-17</div> <div>Near Density</div>
1in:20ft Depth	M55-UBF Sonic CBL with Density Summary					

APPENDIX H

Well Development Forms

DEVELOPMENT FIELD DATA LOG

Project Name: <u>FCI</u>	Project No.: <u>129687-002</u>
Well No.: <u>U55-UBF</u>	Date: <u>4-24-17</u>
Location:	Measuring Point:
Total Depth of Well (ft bls): <u>260</u>	Screen Interval (ft bls): <u>260-240</u>
Pump Type/Setting (ft bls): <u>AirLift, 257</u>	Activity: <u>AirLift</u>
How Q Measured:	H&A Personnel: <u>C Price</u>

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (µmhos/cm)	Temp. °C	Comments
1300								AirLift on, @ 237'
								no recovery, drop to 257'
1315	~1-2							AirLift on
1500								AirLift off, going to recharge 30 min.
1530								AirLift on
1600								AirLift off
1630								AirLift on
1700								AirLift off
1730								AirLift on
1750								AirLift off
4-25 0608	~1-2							AirLift on
0610	1-2			0.3				Dark Brown.
0620	1-2			<0.1				Brown.
0630								AirLift off
0700								AirLift on
0725	1-2			<0.1				Brown.
0730								AirLift off
0800	1-2							AirLift on
0835								AirLift off
0901	1-2							AirLift on
1015				<0.1				AirLift off
								Injecting 1/4 gal
1030								Aqua-Clear
1057								Swabbing
1120								End Swab.
Comments:								

DEVELOPMENT FIELD DATA LOG

Project Name: FLI	Project No.: 129687-002
Well No.: M55-UBF	Date: 5-1-17
Location:	Measuring Point:
Total Depth of Well (ft bls): 260	Screen Interval (ft bls): 260-240
Pump Type/Setting (ft bls): Air Lift 257	Activity: Air Lift
How Q Measured:	H&A Personnel: C Price

[illegible]

DEVELOPMENT FIELD DATA LOG

Project Name: FCI	Project No.: 129687-002
Well No.: MSS-LBF	Date: 5-1-17 through 5-2-17
Location:	Measuring Point: TOM = 2.65' als
Total Depth of Well (ft bls): 260	Screen Interval (ft bls): 260-240
Pump Type/Setting (ft bls): Grundfos, 255'	Activity: Development
How Q Measured: Stopwatch / 5 gal bucket	H&A Personnel: C. Price

Time	Discharge (gpm)	Pumping Water Level (ft)	Specific Capacity (gpm/ft)	Sand Content (ppm)	pH	Sp. Cond. (umhos/cm)	Temp. °C	Comments
1235		235.54						pump on.
1237	20	253.84		0.2	6.61	1589	27.3	Brown drill mud
1238								dry, pump off
1242		235.91						
1244	~20			<0.1	7.26	1567	23.9	dark brown.
1245								dry, pump off
1247		236.00						pump on
1248	~20	252.89		<0.1	7.25	1521	22.7	brown, 761
1249								pump off
1253		241.85	236.00					
1256	~12	241.85						
1259	~12	245.70		<0.1	7.26	1332	23.8	cloudy 112
1302	10	246.50		<0.1	7.25	1532	22.9	clear 48.8
1306	10	245.12		0	7.23	1510	23.1	cloudy 86.4
1315	10	245.84		0	7.20	1513	23.4	clear 19.7
1322	10	245.44		0	7.22	1516	23.7	clear 7.29
1330	10	245.49		0	7.23	151496	23.8	clear 5.69
1346	10	245.68		0	7.19	1489	24.1	clear 4.72
1348								pump off
1435		235.66						
1438	10	239.38		0	7.24	1573	24.1	cloudy 48.4
1440	10	239.61		0	7.19	1512	23.3	clear 13.2
1453	10	240.41		0	7.21	1504	23.9	clear 4.44
1545	10	240.99		0	7.24	1503	24.1	clear 2.28
1600	10	241.05		0	7.19	1502	24.0	clear 3.03
1601								pump off
1630	10	235.60						pump on
1653	10	238.18		0	7.18	1502	24.4	clear 2.23
Comments:								

DEVELOPMENT FIELD DATA LOG

Project Name: <u>FCI</u>	Project No.: <u>129687-002</u>
Well No.: <u>M55-VBF</u>	Date: <u>5-1-17 to 5-2-17</u>
Location:	Measuring Point: <u>TOM 2.65' als</u>
Total Depth of Well (ft bls): <u>260</u>	Screen Interval (ft bls): <u>260-240</u>
Pump Type/Setting (ft bls): <u>Grundfos, 255'</u>	Activity: <u>Development</u>
How Q Measured: <u>stopwatch / 5 gal bucket</u>	H&A Personnel: <u>C. Tricy</u>

[illegible]